Program Version:**EnergyPlus, Version 25.2.0-cf7368216c, YMD=2026.10.22 22:29**

Table of Contents

Tabular Output Report in Format: **HTML**

Building: **Building 1**

Environment: **RUN PERIOD 1 ** Quixeramobim CE BRA INMET WMO#=825860**

Simulation Timestamp: **2026-10-22 22:29:08**

Report: **Annual Building Utility Performance Summary**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Values gathered over 8760.00 hours

Site and Source Energy

	Total Energy [GJ]	Energy Per Total Building Area [MJ/m2]	Energy Per Conditioned Building Area [MJ/m2]
Total Site Energy	9.96	141.31	141.31
Net Site Energy	9.96	141.31	141.31
Total Source Energy	31.54	447.52	447.52
Net Source Energy	31.54	447.52	447.52

Site to Source Energy Conversion Factors

	Site=>Source Conversion Factor
Electricity	3.167
Natural Gas	1.084
District Cooling	1.056
District Heating Water	3.613
District Heating Steam	1.200
Gasoline	1.050
Diesel	1.050
Coal	1.050
Fuel Oil No 1	1.050
Fuel Oil No 2	1.050
Propane	1.050
Other Fuel 1	1.000
Other Fuel 2	1.000

Building Area

	Area [m2]
Total Building Area	70.48
Net Conditioned Building Area	70.48
Unconditioned Building Area	0.00

End Uses

	Electricity [GJ]	Natural Gas [GJ]	Gasoline [GJ]	Diesel [GJ]	Coal [GJ]	Fuel Oil No 1 [GJ]	Fuel Oil No 2 [GJ]	Propane [GJ]	Other Fuel 1 [GJ]	Other Fuel 2 [GJ]	District Cooling [GJ]	District Heating Water [GJ]	District Heating Steam [GJ]	Water [m3]
Heating	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling	6.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	2.49	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	0.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Exterior Equipment	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	0.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total End Uses	9.96	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

End Uses By Subcategory

	Subcategory	Electricity [GJ]	Natural Gas [GJ]	Gasoline [GJ]	Diesel [GJ]	Coal [GJ]	Fuel Oil No 1 [GJ]	Fuel Oil No 2 [GJ]	Propane [GJ]	Other Fuel 1 [GJ]	Other Fuel 2 [GJ]	District Cooling [GJ]	District Heating Water [GJ]	District Heating Steam [GJ]	Water [m3]
Heating	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling	General	6.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	General	2.49	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	General	0.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	General	0.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

End Uses By Space Type

	Space Type	Electricity [GJ]	Natural Gas [GJ]	Gasoline [GJ]	Diesel [GJ]	Coal [GJ]	Fuel Oil No 1 [GJ]	Fuel Oil No 2 [GJ]	Propane [GJ]	Other Fuel 1 [GJ]	Other Fuel 2 [GJ]	District Cooling [GJ]	District Heating Water [GJ]	District Heating Steam [GJ]	Water [m3]
Heating	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling	Unassigned	6.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	LECTURE HALL 1	2.49	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	LECTURE HALL 1	0.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	Unassigned	0.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	Unassigned	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Normalized Metrics

Utility Use Per Conditioned Floor Area

	Electricity Intensity [MJ/m2]	Natural Gas Intensity [MJ/m2]	Gasoline Intensity [MJ/m2]	Diesel Intensity [MJ/m2]	Coal Intensity [MJ/m2]	Fuel Oil No 1 Intensity [MJ/m2]	Fuel Oil No 2 Intensity [MJ/m2]	Propane Intensity [MJ/m2]	Other Fuel 1 Intensity [MJ/m2]	Other Fuel 2 Intensity [MJ/m2]	District Cooling Intensity [MJ/m2]	District Heating Water Intensity [MJ/m2]	District Heating Steam Intensity [MJ/m2]	Water Intensity [m3/m2]
Lighting	35.36	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
HVAC	101.16	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Other	4.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total	141.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Utility Use Per Total Floor Area

	Electricity Intensity [MJ/m2]	Natural Gas Intensity [MJ/m2]	Gasoline Intensity [MJ/m2]	Diesel Intensity [MJ/m2]	Coal Intensity [MJ/m2]	Fuel Oil No 1 Intensity [MJ/m2]	Fuel Oil No 2 Intensity [MJ/m2]	Propane Intensity [MJ/m2]	Other Fuel 1 Intensity [MJ/m2]	Other Fuel 2 Intensity [MJ/m2]	District Cooling Intensity [MJ/m2]	District Heating Water Intensity [MJ/m2]	District Heating Steam Intensity [MJ/m2]	Water Intensity [m3/m2]
Lighting	35.36	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
HVAC	101.16	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Other	4.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Total	141.31	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

Electric Loads Satisfied

	Electricity [GJ]	Percent Electricity [%]
Fuel-Fired Power Generation	0.000	0.00
High Temperature Geothermal*	0.000	0.00
Photovoltaic Power	0.000	0.00
Wind Power	0.000	0.00
Power Conversion	0.000	0.00
Net Decrease in On-Site Storage	0.000	0.00
Total On-Site Electric Sources	0.000	0.00
Electricity Coming From Utility	9.959	100.00
Surplus Electricity Going To Utility	0.000	0.00
Net Electricity From Utility	9.959	100.00
Total On-Site and Utility Electric Sources	9.959	100.00
Total Electricity End Uses	9.959	100.00

On-Site Thermal Sources

	Heat [GJ]	Percent Heat [%]
Water-Side Heat Recovery	0.00	
Air to Air Heat Recovery for Cooling	0.00	
Air to Air Heat Recovery for Heating	0.00	
High-Temperature Geothermal*	0.00	
Solar Water Thermal	0.00	
Solar Air Thermal	0.00	
Total On-Site Thermal Sources	0.00	

Water Source Summary

	Water [m3]	Percent Water [%]
Rainwater Collection	0.00	-
Condensate Collection	0.00	-

Groundwater Well	0.00	-
Total On Site Water Sources	0.00	-
-	-	-
Initial Storage	0.00	-
Final Storage	0.00	-
Change in Storage	0.00	-
-	-	-
Water Supplied by Utility	0.00	-
-	-	-
Total On Site, Change in Storage, and Utility Water Sources	0.00	-
Total Water End Uses	0.00	-

Setpoint Not Met Criteria

	Degrees [deltaC]
Tolerance for Zone Heating Setpoint Not Met Time	0.20
Tolerance for Zone Cooling Setpoint Not Met Time	0.20

Comfort and Setpoint Not Met Summary

	Facility [Hours]
Time Setpoint Not Met During Occupied Heating	0.00
Time Setpoint Not Met During Occupied Cooling	2.67
Time Not Comfortable Based on Simple ASHRAE 55-2004	218.33

Note 1: An asterisk (*) indicates that the feature is not yet implemented.

Table of Contents

Top
Annual Building Utility Performance Summary
Input Verification and Results Summary
Demand End Use Components Summary
Source Energy End Use Components Summary
Component Sizing Summary
Surface Shadowing Summary
Adaptive Comfort Summary
Initialization Summary
Annual Heat Emissions Summary
Annual Thermal Resilience Summary
Climatic Data Summary
Envelope Summary
Shading Summary
Lighting Summary
Equipment Summary
Control Summary
HVAC Sizing Summary
Coil Sizing Details
System Summary
HVAC Topology
Outdoor Air Summary
Outdoor Air Details
Object Count Summary
Energy Meters
Sensible Heat Gain Summary
Standard 62.1 Summary
LEED Summary
Annual CO2 Resilience Summary
Annual Visual Resilience Summary

BUILDING ENERGY PERFORMANCE - ELECTRICITY

| Meter |

BUILDING ENERGY PERFORMANCE - ELECTRICITY PEAK DEMAND

| Meter |

Life-Cycle Cost Report

| Entire Facility |

Report: **Input Verification and Results Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

General

	Value
Program Version and Build	EnergyPlus, Version 25.2.0-cf7368216c, YMD=2026.10.22 22:29
RunPeriod	RUN PERIOD 1
Weather File	Quixeramobim CE BRA INMET WMO#=825860
Latitude [deg]	-5.2
Longitude [deg]	-39.3
Elevation [m]	80.00
Time Zone	-3.0
North Axis Angle [deg]	0.00
Rotation for Appendix G [deg]	0.00
Hours Simulated [hrs]	8760.00

ENVELOPE

Window-Wall Ratio

	Total	North (315 to 45 deg)	East (45 to 135 deg)	South (135 to 225 deg)	West (225 to 315 deg)
Gross Wall Area [m2]	95.15	26.84	20.74	26.84	20.74
Above Ground Wall Area [m2]	95.15	26.84	20.74	26.84	20.74
Window Opening Area [m2]	10.08	10.08	0.00	0.00	0.00
Gross Window-Wall Ratio [%]	10.59	37.55	0.00	0.00	0.00
Above Ground Window-Wall Ratio [%]	10.59	37.55	0.00	0.00	0.00

Conditioned Window-Wall Ratio

	Total	North (315 to 45 deg)	East (45 to 135 deg)	South (135 to 225 deg)	West (225 to 315 deg)
Gross Wall Area [m2]	95.15	26.84	20.74	26.84	20.74
Above Ground Wall Area [m2]	95.15	26.84	20.74	26.84	20.74
Window Opening Area [m2]	10.08	10.08	0.00	0.00	0.00
Gross Window-Wall Ratio [%]	10.59	37.55	0.00	0.00	0.00
Above Ground Window-Wall Ratio [%]	10.59	37.55	0.00	0.00	0.00

Skylight-Roof Ratio

	Total
Gross Roof Area [m2]	70.48
Skylight Area [m2]	0.00
Skylight-Roof Ratio [%]	0.00

PERFORMANCE

Zone Summary

	Area [m2]	Conditioned (Y/N)	Part of Total Floor Area (Y/N)	Volume [m3]	Multipliers	Above Ground Gross Wall Area [m2]	Underground Gross Wall Area [m2]	Window Glass Area [m2]	Opening Area [m2]	Lighting [W/m2]	People [m2 per person]	Plug and Process [W/m2]
THERMAL ZONE 1	70.48	Yes	Yes	198.05	1.00	95.15	0.00	10.08	10.08	12.5938	1.96	0.7535
Total	70.48			198.05		95.15	0.00	10.08	10.08	12.5938	1.96	0.7535
Conditioned Total	70.48			198.05		95.15	0.00	10.08	10.08	12.5938	1.96	0.7535
Unconditioned Total	0.00			0.00		0.00	0.00	0.00	0.00			
Not Part of Total	0.00			0.00		0.00	0.00	0.00	0.00			

Space Summary

	Area [m2]	Conditioned (Y/N)	Part of Total Floor Area (Y/N)	Multipliers	Zone Name	Space Type	Radiant/Solar Enclosure Name	Lighting [W/m2]	People [m2 per person]	Plug and Process [W/m2]	Tags
SPACE 1	70.48	Yes	Yes	1.00	THERMAL ZONE 1	LECTURE HALL 1	SPACE 1	12.5938	1.96	0.7535	
Total	70.48							12.5938	1.96	0.7535	
Conditioned Total	70.48							12.5938	1.96	0.7535	
Unconditioned Total	0.00							0.0000	0.00	0.0000	
Not Part of Total	0.00							0.0000	0.00	0.0000	

Space Type Summary

	Total Area [m2]	Conditioned Area [m2]	Unconditioned Area [m2]	Not Part of Total Area [m2]	Lighting [W/m2]	People [m2 per person]	Plug and Process [W/m2]
LECTURE HALL 1	70.48	70.48	0.00	0.00	12.5938	1.96	0.7535
Total	70.48	70.48	0.00	0.00			

Report: **Demand End Use Components Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

End Uses

	Electricity [W]	Natural Gas [W]	Gasoline [W]	Diesel [W]	Coal [W]	Fuel Oil No 1 [W]	Fuel Oil No 2 [W]	Propane [W]	Other Fuel 1 [W]	Other Fuel 2 [W]	District Cooling [W]	District Heating Water [W]	District Heating Steam [W]	Water [m3/s]
Time of Peak	25-DEC-08:19	-	-	-	-	-	-	-	-	-	-	-	-	-
Heating	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling	1277.49	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	266.28	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	38.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	41.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total End Uses	1623.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

End Uses By Subcategory

	Subcategory	Electricity [W]	Natural Gas [W]	Gasoline [W]	Diesel [W]	Coal [W]	Fuel Oil No 1 [W]	Fuel Oil No 2 [W]	Propane [W]	Other Fuel 1 [W]	Other Fuel 2 [W]	District Cooling [W]	District Heating Water [W]	District Heating Steam [W]	Water [m3/s]
Heating	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Cooling	General	1277.49	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	General	266.28	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	General	38.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	General	41.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Report: **Source Energy End Use Components Summary**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Values gathered over 8760.00 hours

Source Energy End Use Components Summary

	Source Electricity [GJ]	Source Natural Gas [GJ]	Source Gasoline [GJ]	Source Diesel [GJ]	Source Coal [GJ]	Source Fuel Oil No 1 [GJ]	Source Fuel Oil No 2 [GJ]	Source Propane [GJ]	Source Other Fuel 1 [GJ]	Source Other Fuel 2 [GJ]	Source District Cooling [GJ]	Source District Heating Water [GJ]	Source District Heating Steam [GJ]
Heating	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling	21.42	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	7.89	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	1.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	1.16	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total Source Energy End Use Components	31.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Normalized Metrics

Source Energy End Use Components Per Conditioned Floor Area

	Source Electricity [MJ/m2]	Source Natural Gas [MJ/m2]	Source Gasoline [MJ/m2]	Source Diesel [MJ/m2]	Source Coal [MJ/m2]	Source Fuel Oil No 1 [MJ/m2]	Source Fuel Oil No 2 [MJ/m2]	Source Propane [MJ/m2]	Source Other Fuel 1 [MJ/m2]	Source Other Fuel 2 [MJ/m2]	Source District Cooling [MJ/m2]	Source District Heating Water [MJ/m2]	Source District Heating Steam [MJ/m2]
Heating	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Cooling	303.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	112.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	15.14	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	16.48	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total Source Energy End Use Components	447.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Source Energy End Use Components Per Total Floor Area

	Source Electricity [MJ/m2]	Source Natural Gas [MJ/m2]	Source Gasoline [MJ/m2]	Source Diesel [MJ/m2]	Source Coal [MJ/m2]	Source Fuel Oil No 1 [MJ/m2]	Source Fuel Oil No 2 [MJ/m2]	Source Propane [MJ/m2]	Source Other Fuel 1 [MJ/m2]	Source Other Fuel 2 [MJ/m2]	Source District Cooling [MJ/m2]	Source District Heating Water [MJ/m2]	Source District Heating Steam [MJ/m2]
Heating	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling	303.91	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting	112.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment	15.14	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans	16.48	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total Source Energy End Use Components	447.52	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Report: **Component Sizing Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

ZoneHVAC:PackagedTerminalAirConditioner

	Design Size Cooling Supply Air Flow Rate [m3/s]	User-Specified Cooling Supply Air Flow Rate [m3/s]	Design Size Heating Supply Air Flow Rate [m3/s]	User-Specified Heating Supply Air Flow Rate [m3/s]	Design Size No Load Supply Air Flow Rate [m3/s]
R1 AC 36K BTU	0.254852	0.377778	0.254852	0.000000	0.254852

R6 AC 30K BTU	0.254852	0.302778	0.254852	0.000000	0.254852

User-Specified values were used. Design Size values were used if no User-Specified values were provided.

Coil:Cooling:DX:SingleSpeed

	Design Size Rated Air Flow Rate [m3/s]	User-Specified Rated Air Flow Rate [m3/s]	Design Size Gross Rated Total Cooling Capacity [W]	User-Specified Gross Rated Total Cooling Capacity [W]	Design Size Gross Rated Sensible Heat Ratio
ELEC PTAC 1 SPD DX CLG COIL	0.254852	0.377778	6072.60	10551.00	0.669509
ELEC PTAC 1 SPD DX CLG COIL 1	0.254852	0.302778	4867.01	8790.00	0.660155

User-Specified values were used. Design Size values were used if no User-Specified values were provided.

Coil:Heating:Electric

	User-Specified Nominal Capacity [W]
PTAC ELEC HTG COIL	0.000000
PTAC ELEC HTG COIL 1	0.000000

User-Specified values were used. Design Size values were used if no User-Specified values were provided.

Fan:ConstantVolume

	Design Size Maximum Flow Rate [m3/s]	User-Specified Maximum Flow Rate [m3/s]	Design Electric Power Consumption [W]
ELEC PTAC FAN	0.254852	0.377778	26.98
ELEC PTAC FAN 1	0.254852	0.302778	21.63

User-Specified values were used. Design Size values were used if no User-Specified values were provided.

Report: **Surface Shadowing Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Surfaces (Walls, Roofs, etc) that may be Shadowed by Other Surfaces

None	

Subsurfaces (Windows and Doors) that may be Shadowed by Surfaces

	Possible Shadow Receivers
SURFACE 4	SUB SURFACE 2 | SUB SURFACE 3 | SUB SURFACE 4 | SUB SURFACE 5 |
SURFACE 5	SUB SURFACE 1 |

Report: **Adaptive Comfort Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Time Not Meeting the Adaptive Comfort Models during Occupied Hours

	ASHRAE55 90% Acceptability Limits [Hours]	ASHRAE55 80% Acceptability Limits [Hours]	CEN15251 Category I Acceptability Limits [Hours]	CEN15251 Category II Acceptability Limits [Hours]	CEN15251 Category III Acceptability Limits [Hours]

Report: **Initialization Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Version

	Version ID
1	25.2

Timesteps per Hour

	#TimeSteps	Minutes per TimeStep {minutes}
1	6	10

System Convergence Limits

	Minimum System TimeStep {minutes}	Max HVAC Iterations	Minimum Plant Iterations	Maximum Plant Iterations
1	1	20	2	8

Simulation Control

	Do Zone Sizing	Do System Sizing	Do Plant Sizing	Do Design Days	Do Weather Simulation	Do HVAC Sizing Simulation
1	Yes	No	No	Yes	Yes	No

Performance Precision Tradeoffs

	Use Coil Direct Simulation	Zone Radiant Exchange Algorithm	Override Mode	Number of Timestep In Hour	Force Euler Method	Minimum Number of Warmup Days	Force Suppress All Begin Environment Resets	Minimum System Timestep	MaxZoneTempDiff	MaxAllowedDelTemp
1	No	ScriptF	Normal	6	No	1	No	1.0	0.300	2.0000E-003

Output Reporting Tolerances

	Tolerance for Time Heating Setpoint Not Met	Tolerance for Zone Cooling Setpoint Not Met Time
1	0.200	0.200

Site:GroundTemperature:BuildingSurface

	Jan{C}	Feb{C}	Mar{C}	Apr{C}	May{C}	Jun{C}	Jul{C}	Aug{C}	Sep{C}	Oct{C}	Nov{C}	Dec{C}
1	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00	18.00

Site:GroundTemperature:FCfactorMethod

	Jan{C}	Feb{C}	Mar{C}	Apr{C}	May{C}	Jun{C}	Jul{C}	Aug{C}	Sep{C}	Oct{C}	Nov{C}	Dec{C}
1	27.44	28.01	28.15	27.99	27.18	26.29	25.47	24.88	24.73	25.03	25.73	26.59

Site:GroundTemperature:Shallow

	Jan{C}	Feb{C}	Mar{C}	Apr{C}	May{C}	Jun{C}	Jul{C}	Aug{C}	Sep{C}	Oct{C}	Nov{C}	Dec{C}
1	13.00	13.00	13.00	13.00	13.00	13.00	13.00	13.00	13.00	13.00	13.00	13.00

Site:GroundTemperature:Deep

	Jan{C}	Feb{C}	Mar{C}	Apr{C}	May{C}	Jun{C}	Jul{C}	Aug{C}	Sep{C}	Oct{C}	Nov{C}	Dec{C}
1	16.00	16.00	16.00	16.00	16.00	16.00	16.00	16.00	16.00	16.00	16.00	16.00

Site:GroundReflectance

	Jan{dimensionless}	Feb{dimensionless}	Mar{dimensionless}	Apr{dimensionless}	May{dimensionless}	Jun{dimensionless}	Jul{dimensionless}	Aug{dime
1	0.20	0.20	0.20	0.20	0.20	0.20	0.20	

Site:GroundReflectance:SnowModifier

	Normal	Daylighting {dimensionless}
1	1.000	1.000

Site:GroundReflectance:Snow

	Jan{dimensionless}	Feb{dimensionless}	Mar{dimensionless}	Apr{dimensionless}	May{dimensionless}	Jun{dimensionless}	Jul{dimensionless}	Aug{dime
1	0.20	0.20	0.20	0.20	0.20	0.20	0.20	

Site:GroundReflectance:Snow:Daylighting

	Jan{dimensionless}	Feb{dimensionless}	Mar{dimensionless}	Apr{dimensionless}	May{dimensionless}	Jun{dimensionless}	Jul{dimensionless}	Aug{dime
1	0.20	0.20	0.20	0.20	0.20	0.20	0.20	

Environment:Weather Station

	Wind Sensor Height Above Ground {m}	Wind Speed Profile Exponent {}	Wind Speed Profile Boundary Layer Thickness {m}	Air Temperature Sensor Height Above Ground {m}	Wind Speed Modifier Coefficient-Internal	Temperature Modifier Coefficient-Internal
1	10.000	0.140	270.000	1.500	1.586	9.750E-003

Site:Location

	Location Name	Latitude {N+/S- Deg}	Longitude {E+/W- Deg}	Time Zone Number {GMT+/-}	Elevation {m}	Standard Pressure at Elevation {Pa}	Standard RhoAir at Elevation
1	Quixeramobim CE BRA INMET WMO#=825860	-5.20	-39.29	-3.00	80.00	100368	1.1929

Site Water Mains Temperature Information

	Calculation Method{}	Water Mains Temperature Schedule Name{}	Annual Average Outdoor Air Temperature{C}	Maximum Difference In Monthly Average Outdoor Air Temperatures{deltaC}	Fixed Default Water Mains Temperature{C}
1	FixedDefault	NA	NA	NA	10.0

Building Information

	Building Name	North Axis {deg}	Terrain	Loads Convergence Tolerance Value	Temperature Convergence Tolerance Value	Solar Distribution	Maximum Number of Warmup Days	Minimum Number of Warmup Days
1	Building 1	0.000	Suburbs	4.00000E-002	0.40000	FullExterior	25	1

Inside Convection Algorithm

	Algorithm {Simple TARP CeilingDiffuser AdaptiveConvectionAlgorithm}
1	TARP

Outside Convection Algorithm

	Algorithm {SimpleCombined TARP MoWitt DOE-2 AdaptiveConvectionAlgorithm}
1	DOE-2

Sky Radiance Distribution

	Value {Anisotropic}
1	Anisotropic

Zone Air Solution Algorithm

	Algorithm {ThirdOrderBackwardDifference AnalyticalSolution EulerMethod}	Space Heat Balance Sizing	Space Heat Balance Simulation
1	ThirdOrderBackwardDifference	No	No

Zone Air Carbon Dioxide Balance Simulation

	Simulation {Yes/No}	Carbon Dioxide Concentration
1	No	N/A

Zone Air Generic Contaminant Balance Simulation

	Simulation {Yes/No}	Generic Contaminant Concentration
1	No	N/A

Zone Air Mass Flow Balance Simulation

	Enforce Mass Balance	Adjust Zone Mixing and Return {AdjustMixingOnly AdjustReturnOnly AdjustMixingThenReturn AdjustReturnThenMixing None}	Adjust Zone Infiltration {AddInfiltration AdjustInfiltration None}	Infiltration Zones {MixingSourceZonesOnly AllZones}
1	No	N/A	N/A	N/A

HVACSystemRootFindingAlgorithm

	Value {RegulaFalsi Bisection BisectionThenRegulaFalsi RegulaFalsiThenBisection}
1	RegulaFalsi

Environment:Site Atmospheric Variation

	Wind Speed Profile Exponent {}	Wind Speed Profile Boundary Layer Thickness {m}	Air Temperature Gradient Coefficient {K/m}
1	0.220	370.000	6.500000E-003

Shadowing/Sun Position Calculations Annual Simulations

	Shading Calculation Method	Shading Calculation Update Frequency Method	Shading Calculation Update Frequency {days}	Maximum Figures in Shadow Overlap Calculations {}	Polygon Clipping Algorithm	Pixel Counting Resolution	Sky Diffuse Modeling Algorithm	Output External Shading Calculation Results	Disable Self-Shading Within Shading Zone Groups	Disable Self-Shading From Shading Zone Groups to Other Zones
1	PolygonClipping	Periodic	20	15000	SutherlandHodgman	512	SimpleSkyDiffuseModeling	No	No	No

Surface Geometry

	Starting Corner	Vertex Input Direction	Coordinate System	Daylight Reference Point Coordinate System	Rectangular (Simple) Surface Coordinate System
1	UpperLeftCorner	Counterclockwise	RelativeCoordinateSystem	RelativeCoordinateSystem	RelativeToZoneOrigin

Surface Heat Transfer Algorithm

	Value {CTF - ConductionTransferFunction EMPD - MoisturePenetrationDepthConductionTransferFunction CondFD - ConductionFiniteDifference HAMT - CombinedHeatAndMoistureFiniteElement} - Description	Inside Surface Max Temperature Limit{C}	Surface Convection Coefficient Lower Limit {W/m2-K}	Surface Convection Coefficient Upper Limit {W/m2-K}
1	CTF - ConductionTransferFunction	200	0.10	1000.0

Shading Summary

	Number of Fixed Detached Shades	Number of Building Detached Shades	Number of Attached Shades
1	0	0	0

Zone Summary

	Number of Zones	Number of Zone Surfaces	Number of SubSurfaces
1	1	11	5

Zone Information

	Zone Name	North Axis {deg}	Origin X-Coordinate {m}	Origin Y-Coordinate {m}	Origin Z-Coordinate {m}	Centroid X-Coordinate {m}	Centroid Y-Coordinate {m}	Centroid Z-Coordinate {m}	Type	Zone Multiplier	Zone List Multiplier	Minimum X {m}	Maximum X {m}	Minimum Y {m}	M
1	THERMAL ZONE 1	0.0	14.38	28.49	0.00	19.15	24.80	1.40	1	1	1	14.38	23.93	21.11	

Zone Internal Gains Nominal

	Zone Name	Floor Area {m2}	# Occupants	Area per Occupant {m2/person}	Occupant per Area {person/m2}	Interior Lighting {W/m2}	Electric Load {W/m2}	Gas Load {W/m2}	Other Load {W/m2}	Hot Water Eq {W/m2}	Steam Equipment {W/m2}	Sum Loads per Area {W/m2}	Outdoor Controlled Baseboard Heat
1	THERMAL ZONE 1	70.48	36.0	1.958	0.511	12.594	0.753	0.000	0.000	0.000	0.000	13.347	No

People Internal Gains Nominal

	Name	Schedule Name	Zone Name	Zone Floor Area {m2}	# Zone Occupants	Number of People {}	People/Floor Area {person/m2}	Floor Area per person {m2/person}	Fraction Radiant	Fraction Convected	Sensible Fraction Calculation	Activity level	ASHRAE 55 Warnings	G
1	SPACE 1 189.1-2009 - OFFICE - LOBBY - CZ4-8 PEOPLE 1	SCHEDULE RULESET 1 QXD LECTURE HALL OCUPACAO	THERMAL ZONE 1	70.48	36.0	36.0	0.511	1.958	0.300	0.700	AutoCalculate	SCHEDULE RULESET 1 QXD ACTIVITY LEVEL	No	

Lights Internal Gains Nominal

	Name	Schedule Name	Zone Name	Zone Floor Area {m2}	# Zone Occupants	Lighting Level {W}	Lights/Floor Area {W/m2}	Lights per person {W/person}	Fraction Return Air	Fraction Radiant	Fraction Short Wave	Fraction Convected	Fraction Replaceable	End-Use	M I L
1	SPACE 1 LIGHTS 1	SCHEDULE RULESET 1 QXD LECTURE HALL LIGHT	THERMAL ZONE 1	70.48	36.0	887.597	12.594	24.655	0.000	0.000	0.000	1.000	1.000	General	

ElectricEquipment Internal Gains Nominal

	Name	Schedule Name	Zone Name	Zone Floor Area {m2}	# Zone Occupants	Equipment Level {W}	Equipment/Floor Area {W/m2}	Equipment per person {W/person}	Fraction Latent	Fraction Radiant	Fraction Lost	Fraction Convected	En SubCat
1	SPACE 1 ELECTRIC EQUIPMENT 2	SCHEDULE RULESET 1 QXD LECTURE HALL EQUIPAMENTOS	THERMAL ZONE 1	70.48	36.0	53.104	0.753	1.475	0.000	0.000	0.000	1.000	G

ZoneInfiltration Airflow Stats Nominal

	Name	Input Object	Schedule Name	Zone Name	Zone Floor Area {m2}	# Zone Occupants	Design Volume Flow Rate {m3/s}	Volume Flow Rate/Floor Area {m3/s-m2}	Volume Flow Rate/Exterior Surface Area {m3/s-m2}	ACH - Air Changes per Hour	Equation A - Constant Term Coefficient {}	Eq Tem Co
1	SPACE 1 189.1-2009 - OFFICE - LOBBY - CZ4-8 INFILTRATION 1	ZoneInfiltration:DesignFlowRate	OFFICE INFIL QUARTER ON	THERMAL ZONE 1	70.48	36.0	3.810E-002	5.405E-004	2.266E-004	0.693	1.000	

AirFlow Model

	Simple
1	Simple

RoomAir Model

	Zone Name	Mixing/Mundt/UCSDDV/UCSDCV/UCSDUFI/UCSDUFE/User Defined
1	THERMAL ZONE 1	Mixing/Well-Stirred

AirflowNetwork Model:Control

	No Multizone or Distribution/Multizone with Distribution/Multizone without Distribution/Multizone with Distribution only during Fan Operation
1	NoMultizoneOrDistribution

Zone Volume Capacitance Multiplier

	Sensible Heat Capacity Multiplier	Moisture Capacity Multiplier	Carbon Dioxide Capacity Multiplier	Generic Contaminant Capacity Multiplier
1	1.000	1.000	1.000	1.000

Load Timesteps in Zone Design Calculation Averaging Window

	Value
1	6

Heating Sizing Factor Information

	Sizing Factor ID	Value
1	Global	1.25
2	Zone THERMAL ZONE 1	1.25

Cooling Sizing Factor Information

	Sizing Factor ID	Value
1	Global	1.15
2	Zone THERMAL ZONE 1	1.15

Zone Sizing Information

	Zone Name	Load Type	Calc Des Load {W}	User Des Load {W}	Calc Des Air Flow Rate {m3/s}	User Des Air Flow Rate {m3/s}	Design Day Name	Date/Time of Peak	Temperature at Peak {C}	Humidity Ratio at Peak {kgWater/kgDryAir}	Floor Area {m2}	# Occupants	
1	THERMAL ZONE 1	Cooling	1909.56179	2195.99606	0.19619	0.25485	QUIXERAMOBIM SUMMER DESIGN DAY	3/21 16:20:00	35.13333	1.40599E-002	70.47900	36.00000	

2	THERMAL ZONE 1	Heating	0.00000	0.00000	0.00000	0.25485		00:10:00	27.70000	1.40465E-002	70.47900	36.00000	

Component Sizing Information

	Component Type	Component Name	Input Field Description	Value
1	ZoneHVAC:PackagedTerminalAirConditioner	R1 AC 36K BTU	Design Size Cooling Supply Air Flow Rate [m3/s]	0.25485
2	ZoneHVAC:PackagedTerminalAirConditioner	R1 AC 36K BTU	User-Specified Cooling Supply Air Flow Rate [m3/s]	0.37778
3	ZoneHVAC:PackagedTerminalAirConditioner	R1 AC 36K BTU	Design Size Heating Supply Air Flow Rate [m3/s]	0.25485
4	ZoneHVAC:PackagedTerminalAirConditioner	R1 AC 36K BTU	User-Specified Heating Supply Air Flow Rate [m3/s]	1.00000E-011
5	ZoneHVAC:PackagedTerminalAirConditioner	R1 AC 36K BTU	Design Size No Load Supply Air Flow Rate [m3/s]	0.25485
6	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	Design Size Rated Air Flow Rate [m3/s]	0.25485
7	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	User-Specified Rated Air Flow Rate [m3/s]	0.37778
8	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	Design Size Gross Rated Total Cooling Capacity [W]	6072.60172
9	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	User-Specified Gross Rated Total Cooling Capacity [W]	10551.00000
10	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	Design Size Gross Rated Sensible Heat Ratio	0.66951
11	Coil:Heating:Electric	PTAC ELEC HTG COIL	User-Specified Nominal Capacity [W]	0.00000
12	Fan:ConstantVolume	ELEC PTAC FAN	Design Size Maximum Flow Rate [m3/s]	0.25485
13	Fan:ConstantVolume	ELEC PTAC FAN	User-Specified Maximum Flow Rate [m3/s]	0.37778
14	Fan:ConstantVolume	ELEC PTAC FAN	Design Electric Power Consumption [W]	26.98413
15	ZoneHVAC:PackagedTerminalAirConditioner	R6 AC 30K BTU	Design Size Cooling Supply Air Flow Rate [m3/s]	0.25485
16	ZoneHVAC:PackagedTerminalAirConditioner	R6 AC 30K BTU	User-Specified Cooling Supply Air Flow Rate [m3/s]	0.30278
17	ZoneHVAC:PackagedTerminalAirConditioner	R6 AC 30K BTU	Design Size Heating Supply Air Flow Rate [m3/s]	0.25485
18	ZoneHVAC:PackagedTerminalAirConditioner	R6 AC 30K BTU	User-Specified Heating Supply Air Flow Rate [m3/s]	1.00000E-011
19	ZoneHVAC:PackagedTerminalAirConditioner	R6 AC 30K BTU	Design Size No Load Supply Air Flow Rate [m3/s]	0.25485
20	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	Design Size Rated Air Flow Rate [m3/s]	0.25485
21	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	User-Specified Rated Air Flow Rate [m3/s]	0.30278
22	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	Design Size Gross Rated Total Cooling Capacity [W]	4867.01167
23	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	User-Specified Gross Rated Total Cooling Capacity [W]	8790.00000
24	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	Design Size Gross Rated Sensible Heat Ratio	0.66016
25	Coil:Heating:Electric	PTAC ELEC HTG COIL 1	User-Specified Nominal Capacity [W]	0.00000
26	Fan:ConstantVolume	ELEC PTAC FAN 1	Design Size Maximum Flow Rate [m3/s]	0.25485
27	Fan:ConstantVolume	ELEC PTAC FAN 1	User-Specified Maximum Flow Rate [m3/s]	0.30278
28	Fan:ConstantVolume	ELEC PTAC FAN 1	Design Electric Power Consumption [W]	21.62698

DX Cooling Coil Standard Rating Information

	Component Type	Component Name	Standard Rating (Net) Cooling Capacity {W}	Standard Rating Net COP {W/W}	EER {Btu/W-h}	SEER User {Btu/W-h}	SEER Standard {Btu/W-h}	IEER {Btu/W-h}
1	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	10257.2	4.01	13.69	14.51	13.73	14.0
2	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	8554.4	3.57	12.19	12.94	12.24	12.7

DX Cooling Coil AHRI 2023 Standard Rating Information

	Component Type	Component Name	Standard Rating (Net) Cooling Capacity {W}	Standard Rating Net COP2 {W/W}	EER2 {Btu/W-h}	SEER2 User {Btu/W-h}	SEER2 Standard {Btu/W-h}	IEER 2022 {Btu/W-h}
1	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL	10196.3	3.90	13.29	14.08	13.70	13.4
2	Coil:Cooling:DX:SingleSpeed	ELEC PTAC 1 SPD DX CLG COIL 1	8505.7	3.48	11.88	12.60	12.26	12.1

Environment

	Environment Name	Environment Type	Start Date	End Date	Start DayOfWeek	Duration {#days}	Source:Start DayOfWeek	Use Daylight Saving	Use Holidays	Apply Weekend Holiday Rule	Use Rain Values	U Sn Valu

1	QUIXERAMOBIM SUMMER DESIGN DAY	SizingPeriod:DesignDay	03/21	03/21	SummerDesignDay	1	N/A	N/A	N/A	N/A	N/A	N
2	RUN PERIOD 1	WeatherFileRunPeriod	01/01/2006	12/31/2006	Sunday	365	Use RunPeriod Specified Day	No	No	No	Yes	Y

Environment:Daylight Saving

	Daylight Saving Indicator	Source	Start Date	End Date
1	No	SizingPeriod:DesignDay		
2	No	RunPeriod Object		

Environment:WarmupDays

	NumberofWarmupDays
1	3
2	3

Environment:Design Day Data

	Max Dry-Bulb Temp {C}	Temp Range {dC}	Temp Range Ind Type	Hum Ind Type	Hum Ind Value at Max Temp	Hum Ind Units	Pressure {Pa}	Wind Direction {deg CW from N}	Wind Speed {m/s}	Clearness	Rain	Snow
1	36.00	10.00	DefaultMultipliers	Wetbulb	24.00	{C}	100368	0	0.0	0.00	No	No

Environment:Design Day Misc

	DayOfYear	ASHRAE A Coeff	ASHRAE B Coeff	ASHRAE C Coeff	Solar Constant-Annual Variation	Eq of Time {minutes}	Solar Declination Angle {deg}	Solar Model
1	80	1184.3	0.1784	9.3075E-002	1.0	-7.51	-4.2E-002	ASHRAEClearSky

Tabular Report

	Style	Unit Conversion	Format Reals
1	HTML	None	Yes

Warmup Convergence Information

	Zone Name	Environment Type/Name	Average Warmup Temperature Difference {deltaC}	Std Dev Warmup Temperature Difference {deltaC}	Max Temperature Pass/Fail Convergence	Min Temperature Pass/Fail Convergence	Average Warmup Load Difference {W}	Std Dev Warmup Load Difference {W}	Heating Load Pass/Fail Convergence	Cooling Load Pass/Fail Convergence
1	THERMAL ZONE 1	SizingPeriod: QUIXERAMOBIM SUMMER DESIGN DAY	3.1371900669E-002	9.1604647935E-002	Pass	Pass	2.0270335481E-002	0.1190119631	Pass	Pass
2	THERMAL ZONE 1	RunPeriod: RUN PERIOD 1	5.6205154431E-002	3.3769359826E-002	Pass	Pass	0.0000000000	0.0000000000	Pass	Pass

Report: **Annual Heat Emissions Report** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Annual Heat Emissions Summary

	Envelope Convection	Zone Exfiltration	Zone Exhaust Air	HVAC Relief Air	HVAC Reject Heat	Total
Heat Emissions [GJ]	191.77	-5.1	0.00	0.00	37.80	224.49

Report: **Annual Thermal Resilience Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Heat Index Hours

	Safe (≤ 26.7°C) [hr]	Caution (> 26.7°C, ≤ 32.2°C) [hr]	Extreme Caution (> 32.2°C, ≤ 39.4°C) [hr]	Danger (> 39.4°C, ≤ 51.7°C) [hr]	Extreme Danger (> 51.7°C) [hr]
THERMAL ZONE 1	8734.50	25.50	0.00	0.00	0.00
Min	8734.50	25.50	0.00	0.00	0.00
Max	8734.50	25.50	0.00	0.00	0.00
Average	8734.50	25.50	0.00	0.00	0.00
Sum	8734.50	25.50	0.00	0.00	0.00

Heat Index OccupantHours

	Safe (≤ 26.7°C) [hr]	Caution (> 26.7°C, ≤ 32.2°C) [hr]	Extreme Caution (> 32.2°C, ≤ 39.4°C) [hr]	Danger (> 39.4°C, ≤ 51.7°C) [hr]	Extreme Danger (> 51.7°C) [hr]
THERMAL ZONE 1	59529.60	0.00	0.00	0.00	0.00
Min	59529.60	0.00	0.00	0.00	0.00
Max	59529.60	0.00	0.00	0.00	0.00
Average	59529.60	0.00	0.00	0.00	0.00
Sum	59529.60	0.00	0.00	0.00	0.00

Heat Index OccupiedHours

	Safe (≤ 26.7°C) [hr]	Caution (> 26.7°C, ≤ 32.2°C) [hr]	Extreme Caution (> 32.2°C, ≤ 39.4°C) [hr]	Danger (> 39.4°C, ≤ 51.7°C) [hr]	Extreme Danger (> 51.7°C) [hr]
THERMAL ZONE 1	2600.00	0.00	0.00	0.00	0.00
Min	2600.00	0.00	0.00	0.00	0.00
Max	2600.00	0.00	0.00	0.00	0.00
Average	2600.00	0.00	0.00	0.00	0.00
Sum	2600.00	0.00	0.00	0.00	0.00

Humidex Hours

	Little to no Discomfort (≤ 29) [hr]	Some Discomfort (> 29, ≤ 40) [hr]	Great Discomfort; Avoid Exertion (> 40, ≤ 45) [hr]	Dangerous (> 45, ≤ 50) [hr]	Heat Stroke Quite Possible (> 50) [hr]
THERMAL ZONE 1	5159.67	3600.33	0.00	0.00	0.00
Min	5159.67	3600.33	0.00	0.00	0.00
Max	5159.67	3600.33	0.00	0.00	0.00
Average	5159.67	3600.33	0.00	0.00	0.00
Sum	5159.67	3600.33	0.00	0.00	0.00

Humidex OccupantHours

	Little to no Discomfort (≤ 29) [hr]	Some Discomfort (> 29, ≤ 40) [hr]	Great Discomfort; Avoid Exertion (> 40, ≤ 45) [hr]	Dangerous (> 45, ≤ 50) [hr]	Heat Stroke Quite Possible (> 50) [hr]
THERMAL ZONE 1	58155.84	1373.76	0.00	0.00	0.00
Min	58155.84	1373.76	0.00	0.00	0.00
Max	58155.84	1373.76	0.00	0.00	0.00
Average	58155.84	1373.76	0.00	0.00	0.00
Sum	58155.84	1373.76	0.00	0.00	0.00

Humidex OccupiedHours

	Little to no Discomfort (≤ 29) [hr]	Some Discomfort (> 29, ≤ 40) [hr]	Great Discomfort; Avoid Exertion (> 40, ≤ 45) [hr]	Dangerous (> 45, ≤ 50) [hr]	Heat Stroke Quite Possible (> 50) [hr]

THERMAL ZONE 1	2547.00	53.00	0.00	0.00	0.00
Min	2547.00	53.00	0.00	0.00	0.00
Max	2547.00	53.00	0.00	0.00	0.00
Average	2547.00	53.00	0.00	0.00	0.00
Sum	2547.00	53.00	0.00	0.00	0.00

Hours of Safety for Cold Events

	Hours of Safety [hr]	End Time of the Safety Duration	Safe Temperature Exceedance Hours [hr]	Safe Temperature Exceedance OccupantHours [hr]	Safe Temperature Exceedance OccupiedHours [hr]
THERMAL ZONE 1	8760.00	-	0.00	0.00	0.00
Min	8760.00	-	0.00	0.00	0.00
Max	8760.00	-	0.00	0.00	0.00
Average	8760.00	-	0.00	0.00	0.00
Sum	8760.00	-	0.00	0.00	0.00

Hours of Safety for Heat Events

	Hours of Safety [hr]	End Time of the Safety Duration	Safe Temperature Exceedance Hours [hr]	Safe Temperature Exceedance OccupantHours [hr]	Safe Temperature Exceedance OccupiedHours [hr]
THERMAL ZONE 1	8760.00	-	0.00	0.00	0.00
Min	8760.00	-	0.00	0.00	0.00
Max	8760.00	-	0.00	0.00	0.00
Average	8760.00	-	0.00	0.00	0.00
Sum	8760.00	-	0.00	0.00	0.00

Unmet Degree-Hours

	Cooling Setpoint Unmet Degree-Hours [°C·hr]	Cooling Setpoint Unmet Occupant-Weighted Degree-Hours [°C·hr]	Cooling Setpoint Unmet Occupied Degree-Hours [°C·hr]	Heating Setpoint Unmet Degree-Hours [°C·hr]	Heating Setpoint Unmet Occupant-Weighted Degree-Hours [°C·hr]	Heating Setpoint Unmet Occupied Degree-Hours [°C·hr]
THERMAL ZONE 1	48.88	1124.37	48.88	0.00	0.00	0.00
Min	48.88	1124.37	48.88	0.00	0.00	0.00
Max	48.88	1124.37	48.88	0.00	0.00	0.00
Average	48.88	1124.37	48.88	0.00	0.00	0.00
Sum	48.88	1124.37	48.88	0.00	0.00	0.00

Discomfort-weighted Exceedance OccupantHours

	Very-cold Exceedance OccupantHours [hr]	Cool Exceedance OccupantHours [hr]	Warm Exceedance OccupantHours [hr]	Very-hot Exceedance OccupantHours [hr]
THERMAL ZONE 1	0.00	0.00	0.00	0.00
Min	0.00	0.00	0.00	0.00
Max	0.00	0.00	0.00	0.00
Average	0.00	0.00	0.00	0.00
Sum	0.00	0.00	0.00	0.00

Discomfort-weighted Exceedance OccupiedHours

	Very-cold Exceedance OccupantHours [hr]	Cool Exceedance OccupantHours [hr]	Warm Exceedance OccupantHours [hr]	Very-hot Exceedance OccupantHours [hr]
THERMAL ZONE 1	0.00	0.00	0.00	0.00
Min	0.00	0.00	0.00	0.00
Max	0.00	0.00	0.00	0.00
Average	0.00	0.00	0.00	0.00
Sum	0.00	0.00	0.00	0.00

Report: **Climatic Data Summary**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

SizingPeriod:DesignDay

	Maximum Dry Bulb [C]	Daily Temperature Range [deltaC]	Humidity Value	Humidity Type	Wind Speed [m/s]	Wind Direction
QUIXERAMOBIM SUMMER DESIGN DAY	36.00	10.00	24.00	Wetbulb [C]	0.00	0.00

Monthly Precipitation Summary

	Monthly Total Precipitation from .epw [mm]	Monthly Total Hours of Rain from .epw	Monthly Total Precipitation in Site:Precipitation [mm]	Monthly Total Roof Irrigation Depth [mm]	Monthly Total Rain Collection Volume [m3]
Jan	30.00	18			
Feb	81.00	38			
Mar	130.00	62			
Apr	324.00	100			
May	220.00	93			
Jun	87.00	39			
Jul	75.00	38			
Aug	52.00	20			
Sep	1.00	2			
Oct	0.00	0			
Nov	3.00	6			
Dec	28.00	11			

Weather Statistics File

	Value
None	

Report: **Envelope Summary**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Opaque Exterior

	Construction	Zone	Space	Reflectance	U-Factor with Film [W/m2-K]	U-Factor no Film [W/m2-K]	Gross Area [m2]	Net Area [m2]	Azimuth [deg]	Tilt [deg]	Cardinal Direction
SURFACE 2	ASHRAE 189.1-2009 EXTWALL MASS CLIMATEZONE 5	THERMAL ZONE 1	SPACE 1	0.08	0.450	0.483	20.74	20.74	270.00	90.00	W
SURFACE 4	ASHRAE 189.1-2009 EXTWALL MASS CLIMATEZONE 5	THERMAL ZONE 1	SPACE 1	0.08	0.450	0.483	26.84	16.76	0.00	90.00	N
SURFACE 5	ASHRAE 189.1-2009 EXTWALL MASS CLIMATEZONE 5	THERMAL ZONE 1	SPACE 1	0.08	0.450	0.483	26.84	24.32	180.00	90.00	S
SURFACE 6	ASHRAE 189.1-2009 EXTWALL MASS CLIMATEZONE 5	THERMAL ZONE 1	SPACE 1	0.08	0.450	0.483	20.74	20.74	90.00	90.00	E
SURFACE 1	EXTSLABCARPET 4IN CLIMATEZONE 1-8	THERMAL ZONE 1	SPACE 1	0.15	2.945	5.634	70.48	70.48	0.00	180.00	
SURFACE 3	ASHRAE 189.1-2009 EXTROOF IEAD CLIMATEZONE 2-5	THERMAL ZONE 1	SPACE 1	0.30	0.223	0.230	70.48	70.48	0.00	0.00	

Opaque Interior

	Construction	Zone	Space	Adjacent Surface	Reflectance	U-Factor with Film [W/m2-K]	U-Factor no Film [W/m2-K]	Gross Area [m2]	Net Area [m2]	Azimuth [deg]	Tilt [deg]	Cardinal Direction
None												

Exterior Fenestration

	Construction	Zone	Space	Frame and Divider	Glass Area [m2]	Frame Area [m2]	Divider Area [m2]	Area of One Opening [m2]	Area of Multiplied Openings [m2]	Glass U-Factor [W/m2-K]	Glass SHGC	Glass Visible Transmittance	Cond [W
SUB SURFACE 2	VIDRO_FUME_LABORATORIO	THERMAL ZONE 1	SPACE 1		2.52	0.00	0.00	2.52	2.52	5.894	0.522	0.301	
SUB SURFACE 3	VIDRO_FUME_LABORATORIO	THERMAL ZONE 1	SPACE 1		2.52	0.00	0.00	2.52	2.52	5.894	0.522	0.301	
SUB SURFACE 4	VIDRO_FUME_LABORATORIO	THERMAL ZONE 1	SPACE 1		2.52	0.00	0.00	2.52	2.52	5.894	0.522	0.301	
SUB SURFACE 5	VIDRO_FUME_LABORATORIO	THERMAL ZONE 1	SPACE 1		2.52	0.00	0.00	2.52	2.52	5.894	0.522	0.301	
Total or Average									10.08	5.894	0.522	0.301	
North Total or Average									10.08	5.894	0.522	0.301	
Non-North Total or Average									0.00	-	-	-	

Exterior Fenestration Shaded State

	Frame and Divider	Glass U-Factor [W/m2-K]	Glass SHGC	Glass Visible Transmittance	NFRC Product Type	Assembly U-Factor [W/m2-K]	Assembly SHGC	Assembly Visible Transmittance
None								

Interior Fenestration

	Construction	Zone	Space	Area of One Opening [m2]	Area of Openings [m2]	Glass U-Factor [W/m2-K]	Glass SHGC	Glass Visible Transmittance	Parent Surface
Total or Average					0.00	-	-	-	

Exterior Door

	Construction	Zone	Space	U-Factor with Film [W/m2-K]	U-Factor no Film [W/m2-K]	Gross Area [m2]	Parent Surface
SUB SURFACE 1	EXTERIOR DOOR	THERMAL ZONE 1	SPACE 1	1.004	1.181	2.52	SURFACE 5

Interior Door

	Construction	Zone	Space	U-Factor with Film [W/m2-K]	U-Factor no Film [W/m2-K]	Gross Area [m2]	Parent Surface
None							

Opaque Construction Layers

	Layer 1	Layer 2	Layer 3	Layer 4	Layer 5	Layer 6	Layer 7	Layer 8	Layer 9	Layer 10
ASHRAE 189.1-2009 EXTROOFIEAD CLIMATEZONE 2-5	Roof Membrane	Roof Insulation [21]	Metal Decking							
ASHRAE 189.1-2009 EXTWALL MASS CLIMATEZONE 5	1IN Stucco	8IN Concrete HW	Wall Insulation [40]	1/2IN Gypsum						

EXTERIOR DOOR	F08 Metal surface	I01 25mm insulation board								
EXTSLABCARPET 4IN CLIMATEZONE 1-8	MAT-CC05 4 HW CONCRETE	CP02 CARPET PAD								

Report: **Shading Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Sunlit Fraction

	March 21 9am	March 21 noon	March 21 3pm	June 21 9am	June 21 noon	June 21 3pm	December 21 9am	December 21 noon	December 21 3pm
SUB SURFACE 2	0.00	1.00	1.00	1.00	1.00	1.00	0.00	0.00	0.00
SUB SURFACE 3	0.00	1.00	1.00	1.00	1.00	1.00	0.00	0.00	0.00
SUB SURFACE 4	0.00	1.00	1.00	1.00	1.00	1.00	0.00	0.00	0.00
SUB SURFACE 5	0.00	1.00	1.00	1.00	1.00	1.00	0.00	0.00	0.00

Window Control

	Name	Type	Shaded Construction	Control	Glare Control
None					

Report: **Lighting Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Interior Lighting

	Zone Name	Space Name	Space Type	Lighting Power Density [W/m2]	Space Area [m2]	Total Power [W]	End Use Subcategory	Schedule Name	Scheduled Hours/Week [hr]	Hours/Week > 1% [hr]	Full Load Hours/Week [hr]	Return Air Fraction	Conditioned (Y/N)
SPACE 1 LIGHTS 1	THERMAL ZONE 1	SPACE 1	LECTURE HALL 1	12.5938	70.48	887.60	General	SCHEDULE RULESET 1 QXD LECTURE HALL LIGHT	14.96	49.86	14.96	0.0000	Y
Interior Lighting Total				12.5938	70.48	887.60							

Daylighting

	Zone	Control Name	Daylighting Method	Control Type	Fraction Controlled	Lighting Installed in Zone [W]	Lighting Controlled [W]
None							

Exterior Lighting

	Total Watts	Astronomical Clock/Schedule	Schedule Name	Scheduled Hours/Week [hr]	Hours/Week > 1% [hr]	Full Load Hours/Week [hr]	Consumption [GJ]
Exterior Lighting Total	0.00						0.00

Report: **Equipment Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Central Plant

	Type	Reference Capacity [W]	Reference Efficiency [W/W]	Rated Capacity [W]	Rated Efficiency [W/W]	IPLV in SI Units [W/W]	IPLV in IP Units [Btu/W-h]
None							

Cooling Coils

	Type	Design Coil Load [W]	Nominal Total Capacity [W]	Nominal Sensible Capacity [W]	Nominal Latent Capacity [W]	Nominal Sensible Heat Ratio	Nominal Efficiency [W/W]	Nominal Coil UA Value [W/C]	Nominal Coil Surface Area [m2]
ELEC PTAC 1 SPD DX CLG COIL	Coil:Cooling:DX:SingleSpeed		10551.00	7063.99	3487.01	0.67	4.66		
ELEC PTAC 1 SPD DX CLG COIL 1	Coil:Cooling:DX:SingleSpeed		8790.00	5802.76	2987.24	0.66	4.07		

Nominal values are gross at rated conditions, i.e., the supply air fan heat and electric power NOT accounted for.

DX Cooling Coil Standard Ratings 2017

	Cooling Coil Type (1)	Standard Rating Net Cooling Capacity [W] [2]	Standard Rating Net COP [W/W][2]	EER [Btu/W-h] [2]	SEER User [Btu/W-h][2,3]	SEER Standard [Btu/W-h][2,3]	IEER [Btu/W-h] [2]
ELEC PTAC 1 SPD DX CLG COIL	Coil:Cooling:DX:SingleSpeed	10257.2	4.01	13.69	14.51	13.73	14.0
ELEC PTAC 1 SPD DX CLG COIL 1	Coil:Cooling:DX:SingleSpeed	8554.4	3.57	12.19	12.94	12.24	12.7

ANSI/AHRI ratings account for supply air fan heat and electric power.

1. *EnergyPlus object type.*
2. *Capacity less than 65K Btu/h (19050 W) - calculated as per AHRI Standard 210/240-2017.*
   Capacity of 65K Btu/h (19050 W) to less than 135K Btu/h (39565 W) - calculated as per AHRI Standard 340/360-2007.
   Capacity from 135K (39565 W) to 250K Btu/hr (73268 W) - calculated as per AHRI Standard 365-2009 - Ratings not yet supported in EnergyPlus.
3. *SEER (User) is calculated using user-input PLF curve and cooling coefficient of degradation.*
   SEER (Standard) is calculated using the default PLF curve and cooling coefficient of degradation from the appropriate AHRI standard.

DX Cooling Coil Standard Ratings 2023

	Cooling Coil Type (1)	Standard Rating Net Cooling Capacity [W] [2]	Standard Rating Net COP2 [W/W][2,4]	EER2 [Btu/W-h] [2,4]	SEER2 User [Btu/W-h][2,3]	SEER2 Standard [Btu/W-h][2,3]	IEER [Btu/W-h] [2]
ELEC PTAC 1 SPD DX CLG COIL	Coil:Cooling:DX:SingleSpeed	10196.3	3.90	13.29	14.08	13.70	13.4
ELEC PTAC 1 SPD DX CLG COIL 1	Coil:Cooling:DX:SingleSpeed	8505.7	3.48	11.88	12.60	12.26	12.1

ANSI/AHRI ratings account for supply air fan heat and electric power.

1. *EnergyPlus object type.*
2. *Capacity less than 65K Btu/h (19050 W) - calculated as per AHRI Standard 210/240-2023.*
   Capacity of 65K Btu/h (19050 W) to less than 135K Btu/h (39565 W) - calculated as per AHRI Standard 340/360-2022.
   Capacity from 135K (39565 W) to 250K Btu/hr (73268 W) - calculated as per AHRI Standard 365-2009 - Ratings not yet supported in EnergyPlus.
3. *SEER2 (User) is calculated using user-input PLF curve and cooling coefficient of degradation.*
   SEER2 (Standard) is calculated using the default PLF curve and cooling coefficient of degradation from the appropriate AHRI standard.
4. *Value for the Full Speed of the coil.*

DX Cooling Coil ASHRAE 127 Standard Ratings Report

	DX Cooling Coil Type	Rated Net Cooling Capacity Test A [W]	Rated Electric Power Test A [W]	Rated Net Cooling Capacity Test B [W]	Rated Electric Power Test B [W]	Rated Net Cooling Capacity Test C [W]	Rated Electric Power Test C [W]	Rated Net Cooling Capacity Test D [W]	Rated Electric Power Test D [W]
None									

Heat Pump ACCA Manual S Report

	Heat Pump Name	Heat Pump Type	Heat Pump Coil Type	Sizing Method	Total Load	Sensible Load	Total Capacity	Sensible Capacity	Total Capacity Sizing Factor	Sensible Capacity Sizing Factor	Latent Capacity Sizing Factor
None											

Water-to-Air Heat Pumps at Rated Temperatures Report

	Coil Type	Rated Total Capacity [W]	Rated Sensible Capacity [W]	Rated Power[W]	Rated COP [W/W]	Rated Air Dry-bulb Temperature [C]	Rated Air Wet-bulb Temperature [C]	Rated Water Temperature [C]	Design Day used for Sizing
None									

DX Heating Coils

	DX Heating Coil Type	Heating to Cooling Capacity Sizing Ratio	High Temperature Heating (net) Rating Capacity [W]	Low Temperature Heating (net) Rating Capacity [W]	HSPF [Btu/W-h]	Region Number	Minimum Outdoor Dry-Bulb Temperature for Compressor Operation [C]	Supplemental Heat High Shutoff Temperature [C]	Airloop Name
None									

DX Heating Coils AHRI 2023

	DX Heating Coil Type	High Temperature Heating (net) Rating Capacity [W]	Low Temperature Heating (net) Rating Capacity [W]	HSPF2 [Btu/W-h]	Region Number	Minimum Outdoor Dry-Bulb Temperature for Compressor Operation [C]	Airloop Name
None							

Heating Coils

	Type	Design Coil Load [W]	Nominal Total Capacity [W]	Nominal Efficiency [W/W]	Used as Supplementary Heat	Airloop Name	Plantloop Name
PTAC ELEC HTG COIL	Coil:Heating:Electric		0.00	1.00	No	N/A	N/A
PTAC ELEC HTG COIL 1	Coil:Heating:Electric		0.00	1.00	No	N/A	N/A

Fans

	Type	Total Efficiency [W/W]	Delta Pressure [pa]	Max Air Flow Rate [m3/s]	Rated Electricity Rate [W]	Rated Power Per Max Air Flow Rate [W-s/m3]	Motor Heat In Air Fraction	Fan Energy Index	End Use Subcategory	Design Day Name for Fan Sizing Peak	Date/Time for Fan Sizing Peak	Purpose	Is Autosized
ELEC PTAC FAN	Fan:ConstantVolume	0.70	50.00	0.38	26.98	71.43	1.00	7.40	General	QUIXERAMOBIM SUMMER DESIGN DAY	3/21 16:20:00	N/A	Yes
ELEC PTAC FAN 1	Fan:ConstantVolume	0.70	50.00	0.30	21.63	71.43	1.00	8.18	General	QUIXERAMOBIM SUMMER DESIGN DAY	3/21 16:20:00	N/A	Yes

Fan Power Fractions

	Type	Flow Frac 0.0	Flow Frac 0.1	Flow Frac 0.2	Flow Frac 0.3	Flow Frac 0.4	Flow Frac 0.5	Flow Frac 0.6	Flow Frac 0.7	Flow Frac 0.8	Flow Frac 0.9	Flow Frac 1.0
ELEC PTAC FAN	Fan:ConstantVolume	0.00	0.10	0.20	0.30	0.40	0.50	0.60	0.70	0.80	0.90	1.00
ELEC PTAC FAN 1	Fan:ConstantVolume	0.00	0.10	0.20	0.30	0.40	0.50	0.60	0.70	0.80	0.90	1.00

Values are the fraction of full-load power at each flow fraction including any part-load adjustments specified in the fan object.

Pumps

	Type	Control	Head [pa]	Water Flow [m3/s]	Electricity Rate [W]	Power Per Water Flow Rate [W-s/m3]	Motor Efficiency [W/W]	End Use Subcategory	Is Autosized	Plantloop Name	Plantloop Branch Name

None											

Service Water Heating

	Type	Storage Volume [m3]	Input [W]	Thermal Efficiency [W/W]	Recovery Efficiency [W/W]	Energy Factor	Fuel Type	Set Point Schedule Name for Heater 1	Set Point at 11am First Wednesday for Heater 1 [C]	Days with Same 11am Value for Heater 1	Month Assumed for Heater 1	Set Point Schedule Name for Heater 2	Set Point at 11am First Wednesday for Heater 2 [C]	Days with Same 11am Value for Heater 2	Month Assumed for Heater 2	Peak Use Water Flow Rate [m3/s]	Fra Sch
None																	

Water Use

	Zone	End-Use Subcategory	WaterUse Connection Name	Peak Water Flow Rate [m3/s]	Peak Flow Multipler Schedule	Peak Flow Multipler Schedule Maximum	Target Temperature Schedule	Target Temperature Schedule Maximum [C]	Hot Supply Temperature Schedule	Hot Supply Temperature Schedule Maximum [C]	Cold Supply Temperature Schedule	Cold Supply Temperature Schedule Minimum [C]	Sensible Fraction Schedule
None													

WaterUse Connections

	Drain Water Heat Exchanger Type	Drain Water Heat Exchanger Destination	Drain Water Heat Exchanger U-Factor Times Area	Average Heat Recovery Effectiveness	Hot Water Supply Temperature Schedule	Hot Water Supply Temperature Schedule Maximum [C]	Cold Water Supply Temperature Schedule	Cold Water Supply Temperature Schedule Minimum [C]	PlantLoop Name	Branch Name	Supply Water Storage Tank Name	Reclamation Water Storage Tank Name
None												

Chillers

	Type	Reference Capacity[W]	TypeReference Efficiency [W/W]	Rated Capacity [W]	Rated Efficiency [W/W]	IPLV in SI Units [W/W]	IPLV in IP Units [Btu/W-h]	Minimum Part Load Ratio	Fuel Type	Rated Entering Condenser Temperature [C]	Rated Leaving Evaporator Temperature [C]	Reference Entering Condenser Temperature [C]	Reference Leaving Evaporator Temperature [C]	De Refere Chi W F [k
None														

Boilers

	Type	Reference Capacity [W]	Reference Efficiency[W/W]	Rated Capacity [W]	Rated Efficiency [W/W]	Minimum Part Load Ratio	Fuel Type	Parasitic Electric Load [W]	Plantloop Name	Plantloop Branch Name
None										

AWHPs

	Type	Reference Capacity[W]	Reference COP	Minimum Part Load Ratio	Design Size Reference Air Temperature [C]	Entering Water Temperature [C]	Leaving Water Temperature [C]	Design Size Reference Air Flow Rate [kg/s]	Design Size Reference Water Flow Rate [kg/s]	Plantloop Name	Plantloop Branch Name
None											

Cooling Towers and Fluid Coolers

	Type	Fluid Type	Range [C]	Approach [C]	Design Fan Power [W]	Design Inlet Air Wet-Bulb Temperature [C]	Design Water Flow Rate [m3/s]	Leaving Water Setpoint Temperature [C]	Condenser Loop Name	Condenser Loop Branch Name
None										

PlantLoop or CondenserLoop

	Type	Provides Heating	Provides Cooling	Maximum Loop Flow Rate [m3/s]	Minimum Loop Flow Rate [m3/s]	Design Supply Temperature [C]	Design Return Temperature [C]	Design Capacity [W]
None								

Air Terminals

	Zone Name	Minimum Flow [m3/s]	Minimum Outdoor Flow [m3/s]	Supply Cooling Setpoint [C]	Supply Heating Setpoint [C]	Heating Capacity [W]	Cooling Capacity [W]	Type of Input Object	Heat/Reheat Coil Object Type	Chilled Water Coil Object Type	PIU Heating Control Type	Fan Object Type	Fan Name	PIU Fan Control Type	Primary Air Flow Rate [m3/s]	Secondary Air Flow Rate [m3/s]	M
None																	

Air Heat Recovery

	Type	Plate/Rotary	Heat Recovery Active	Sensible Effectiveness at 100% Heating Air Flow	Sensible Effectiveness at 100% Cooling Air Flow	Latent Effectiveness at 100% Heating Air Flow	Latent Effectiveness at 100% Cooling Air Flow	Supply Air Flow Rate [m3/s]	Exhaust Air Flow Rate [m3/s]	Zone HVAC Name	Airloop Name	OA System Name	OA Controller Name
None													

Report: **Control Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

SetpointManager:OutdoorAirReset

	Setpoint Nodes	Setpoint Node PlantLoop Name	Control Type	Setpoint at Outdoor Low Temperature [C]	Setpoint at Outdoor High Temperature [C]	Outdoor Low Temperature [C]	Outdoor High Temperature [C]	Schedule Name	Setpoint at Outdoor Low Temperature 2 [C]	Setpoint at Outdoor High Temperature 2 [C]	Outdoor Low Temperature 2 [C]	Outdoor High Temperature 2 [C]
None												

SetpointManager:ReturnTemperature

	Type	Plant Loop Supply Outlet Node	Plant Loop Supply Inlet Node	PlantLoop Name	Minimum Supply Temperature Setpoint [C]	Maximum Supply Temperature Setpoint [C]	Return Temperature Setpoint Input Type	Return Temperature Setpoint [C]	Return Temperature Setpoint Schedule Name
None									

AvailabilityManager:Scheduled

	AvailabilityManager Name	Type	Schedule Name
None			

PlantEquipmentOperation Load Based

	Plant Loop Name	Name	Type	Schedule Name	Index	Lower Limit [W]	Upper Limit [W]	Equipment List Name	Equipment
None									

Report: **HVAC Sizing Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Space Sensible Cooling

	Calculated Design Load [W]	User Design Load [W]	User Design Load per Area [W/m2]	Calculated Design Air Flow [m3/s]	User Design Air Flow [m3/s]	Design Day Name	Date/Time Of Peak {TIMESTAMP}	Thermostat Setpoint Temperature at Peak Load [C]	Indoor Temperature at Peak Load [C]	Indoor Humidity Ratio at Peak Load [kgWater/kgDryAir]	Outdoor Temperature at Peak Load [C]	Outdoor Humi Ratio at Peak L [kgWater/kgDry

None												

The Design Load is the space sensible load only. It does not include any system effects or ventilation loads. Values shown include multipliers.

Zone Sensible Cooling

	Calculated Design Load [W]	User Design Load [W]	User Design Load per Area [W/m2]	Calculated Design Air Flow [m3/s]	User Design Air Flow [m3/s]	Design Day Name	Date/Time Of Peak {TIMESTAMP}	Thermostat Setpoint Temperature at Peak Load [C]	Indoor Temperature at Peak Load [C]	Indoor Humidity Ratio at Peak Load [kgWater/kgDryAir]	Outdc Temperatu at Pe Load [
THERMAL ZONE 1	1909.56	2196.00	31.16	0.196	0.255	QUIXERAMOBIM SUMMER DESIGN DAY	3/21 16:20:00	22.00	21.99	0.01012	35.

The Design Load is the zone sensible load only. It does not include any system effects or ventilation loads. Values shown include multipliers.

Space Sensible Heating

	Calculated Design Load [W]	User Design Load [W]	User Design Load per Area [W/m2]	Calculated Design Air Flow [m3/s]	User Design Air Flow [m3/s]	Design Day Name	Date/Time Of Peak {TIMESTAMP}	Thermostat Setpoint Temperature at Peak Load [C]	Indoor Temperature at Peak Load [C]	Indoor Humidity Ratio at Peak Load [kgWater/kgDryAir]	Outdoor Temperature at Peak Load [C]	Outdoor Humi Ratio at Peak L [kgWater/kgDry
None												

The Design Load is the space sensible load only. It does not include any system effects or ventilation loads. Values shown include multipliers.

Zone Sensible Heating

	Calculated Design Load [W]	User Design Load [W]	User Design Load per Area [W/m2]	Calculated Design Air Flow [m3/s]	User Design Air Flow [m3/s]	Design Day Name	Date/Time Of Peak {TIMESTAMP}	Thermostat Setpoint Temperature at Peak Load [C]	Indoor Temperature at Peak Load [C]	Indoor Humidity Ratio at Peak Load [kgWater/kgDryAir]	Outdoor Temperature at Peak Load [C]	Outdoor Ratio at [kgWater/
THERMAL ZONE 1	0.00	0.00	0.00	0.000	0.255		00:10:00	15.00	21.97	0.01350	27.70	

The Design Load is the zone sensible load only. It does not include any system effects or ventilation loads. Values shown include multipliers.

System Design Air Flow Rates

	Calculated cooling [m3/s]	User cooling [m3/s]	Calculated heating [m3/s]	User heating [m3/s]	Adjusted cooling [m3/s]	Adjusted heating [m3/s]	Adjusted main [m3/s]	Calculated Heating Air Flow Ratio []	User Heating Air Flow Ratio []
None									

Plant Loop Coincident Design Fluid Flow Rate Adjustments

	Previous Design Volume Flow Rate [m3/s]	Algorithm Volume Flow Rate [m3/s]	Coincident Design Volume Flow Rate [m3/s]	Coincident Size Adjusted	Peak Sizing Period Name	Peak Day into Period {TIMESTAMP}[day]	Peak Hour Of Day {TIMESTAMP}[hr]	Peak Step Start Minute {TIMESTAMP}[min]
None								

Coil Sizing Summary

	Coil Type	HVAC Type	HVAC Name	Coil Final Gross Total Capacity [W]	Coil Final Gross Sensible Capacity [W]	Coil Final Reference Air Volume Flow Rate [m3/s]	Coil Final Reference Plant Fluid Volume Flow Rate [m3/s]	Coil U valu Time Are Valu [W/K
ELEC PTAC 1 SPD DX CLG COIL	Coil:Cooling:DX:SingleSpeed	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	10551.000	7063.992	0.377778	-999.0	-999.000

PTAC ELEC HTG COIL	COIL:HEATING:ELECTRIC	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	0.000	0.000	-999.0	-999.0	-999.000
ELEC PTAC 1 SPD DX CLG COIL 1	Coil:Cooling:DX:SingleSpeed	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	8790.000	5802.762	0.302778	-999.0	-999.000
PTAC ELEC HTG COIL 1	COIL:HEATING:ELECTRIC	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	0.000	0.000	-999.0	-999.0	-999.000

Report: **Coil Sizing Details**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Coils

	Coil Type	Coil Location	HVAC Type	HVAC Name	Zone Name(s)	System Sizing Method Concurrence	System Sizing Method Capacity	Sys Si Met F
ELEC PTAC 1 SPD DX CLG COIL	Coil:Cooling:DX:SingleSpeed	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	THERMAL ZONE 1	N/A	N/A	
PTAC ELEC HTG COIL	COIL:HEATING:ELECTRIC	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	THERMAL ZONE 1	N/A	N/A	
ELEC PTAC 1 SPD DX CLG COIL 1	Coil:Cooling:DX:SingleSpeed	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	THERMAL ZONE 1	N/A	N/A	
PTAC ELEC HTG COIL 1	COIL:HEATING:ELECTRIC	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	THERMAL ZONE 1	N/A	N/A	

Coil Connections

	Coil Name	Coil Type	Coil Location	HVAC Type	HVAC Name	Zone Name(s)	Supply Fan Name for HVAC	Supply Fan
ELEC PTAC 1 SPD DX CLG COIL	ELEC PTAC 1 SPD DX CLG COIL	Coil:Cooling:DX:SingleSpeed	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	THERMAL ZONE 1	ELEC PTAC FAN	Fan:Constar

PTAC ELEC HTG COIL	PTAC ELEC HTG COIL	COIL:HEATING:ELECTRIC	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	THERMAL ZONE 1	ELEC PTAC FAN	Fan:Constar
ELEC PTAC 1 SPD DX CLG COIL 1	ELEC PTAC 1 SPD DX CLG COIL 1	Coil:Cooling:DX:SingleSpeed	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	THERMAL ZONE 1	ELEC PTAC FAN 1	Fan:Constar
PTAC ELEC HTG COIL 1	PTAC ELEC HTG COIL 1	COIL:HEATING:ELECTRIC	Zone Equipment	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	THERMAL ZONE 1	ELEC PTAC FAN 1	Fan:Constar

---

Report: **System Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Economizer

	High Limit Shutoff Control	Minimum Outdoor Air [m3/s]	Maximum Outdoor Air [m3/s]	Return Air Temp Limit	Return Air Enthalpy Limit	Outdoor Air Temperature Limit [C]	Outdoor Air Enthalpy Limit [C]	AirLoopHVAC:OutdoorAirSystem Name
None								

Demand Controlled Ventilation using Controller:MechanicalVentilation

	Controller:MechanicalVentilation Name	Outdoor Air Per Person [m3/s-person]	Outdoor Air Per Area [m3/s-m2]	Outdoor Air Per Zone [m3/s]	Outdoor Air ACH [ach]	Outdoor Air Method	Outdoor Air Schedule Name	Air Distribution Effectiveness in Cooling Mode	Air Distribution Effectiveness in Heating Mode	Air Distribution Effectiveness Schedule Name	Type
None											

Time Not Comfortable Based on Simple ASHRAE 55-2004

	Winter Clothes [hr]	Summer Clothes [hr]	Summer or Winter Clothes [hr]
THERMAL ZONE 1	218.33	2600.00	218.33
Facility	218.33	2600.00	218.33

Aggregated over the RunPeriods for Weather

Time Setpoint Not Met

	During Heating [hr]	During Cooling [hr]	During Occupied Heating [hr]	During Occupied Cooling [hr]
THERMAL ZONE 1	0.00	2.67	0.00	2.67
Facility	0.00	2.67	0.00	2.67

Aggregated over the RunPeriods for Weather

Thermostat Schedules

	Thermostat Name 1	Control Type Schedule	Control Type	Control Type Name	Heating Schedule	Cooling Schedule
THERMAL ZONE 1	THERMAL ZONE 1 THERMOSTAT	THERMAL ZONE 1 THERMOSTAT SCHEDULE	DualSetPointWithDeadBand	THERMOSTAT SETPOINT DUAL SETPOINT 1	SCHEDULE RULESET 1 QXD LECTURE HALL HEATING SETPOINT TEMPERATURE	SCHEDULE RULESET 1 QXD LECTURE HALL COOLING SETPOINT TEMPERATURE

Fan Operation

	Occupied Time [hr]	Occupied Continuous Fan [hr]	Occupied Cycling Fan [hr]	Occupied Fan Off [hr]	Unoccupied Time [hr]	Unoccupied Continuous Fan [hr]	Unoccupied Cycling Fan [hr]	Unoccupied Fan Off [hr]
None								

Report: **HVAC Topology**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Air Loop Supply Side Component Arrangement

	Airloop Name	Splitter Name	Supply Branch Name	Supply Branch Type	Component Type	Component Name	Sub-Component Type	Sub-Component Name	Sub-Sub-Component Type	Sub-Sub-Component Name	Mixer Name
None											

Air Loop Demand Side Component Arrangement

	Airloop Name	Supply Branch Name	Supply Branch Type	Supply Path Component Type	Supply Path Component Name	Terminal Unit Type	Terminal Unit Name	Zone Name	Return Path Component Type	Return Path Component Name
None										

Zone Equipment Component Arrangement

	Zone Name	Component Type	Component Name	Sub-Component Type	Sub-Component Name	Sub-Sub-Component Type	Sub Comp
1	THERMAL ZONE 1						
2	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU				
3	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	COIL:COOLING:DX:SINGLESPEED	ELEC PTAC 1 SPD DX CLG COIL		
4	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	COIL:HEATING:ELECTRIC	PTAC ELEC HTG COIL		
5	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R1 AC 36K BTU	FAN:CONSTANTVOLUME	ELEC PTAC FAN		
6	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU				
7	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	COIL:COOLING:DX:SINGLESPEED	ELEC PTAC 1 SPD DX CLG COIL 1		
8	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	COIL:HEATING:ELECTRIC	PTAC ELEC HTG COIL 1		
9	THERMAL ZONE 1	ZONEHVAC:PACKAGEDTERMINALAIRCONDITIONER	R6 AC 30K BTU	FAN:CONSTANTVOLUME	ELEC PTAC FAN 1		

Plant Loop Component Arrangement

	Loop Type	Loop Name	Side	Splitter Name	Branch Name	Component Type	Component Name	Mixer Name
None								

Report: **Outdoor Air Summary**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Average Outdoor Air During Occupied Hours

	Average Number of Occupants	Nominal Number of Occupants	Zone Volume [m3]	Mechanical Ventilation [ach]	Infiltration [ach]	AFN Infiltration [ach]	Simple Ventilation [ach]
THERMAL ZONE 1	22.90	36.00	198.05	0.000	0.168	0.000	0.000

Values shown for a single zone without multipliers

Minimum Outdoor Air During Occupied Hours

	Average Number of Occupants	Nominal Number of Occupants	Zone Volume [m3]	Mechanical Ventilation [ach]	Infiltration [ach]	AFN Infiltration [ach]	Simple Ventilation [ach]
THERMAL ZONE 1	22.90	36.00	198.05	0.000	0.007	0.000	0.000

Values shown for a single zone without multipliers

Report: **Outdoor Air Details** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Mechanical Ventilation Parameters by Zone

	AirLoop Name	Average Number of Occupants	Nominal Number of Occupants	Zone Volume [m3]	Zone Area [m2]	Design Zone Outdoor Airflow - Voz [m3/s]	Minimum Dynamic Target Ventilation - Voz-dyn-min [m3/s]	Zone Multiplier
THERMAL ZONE 1		22.90	36.00	198.05	70.48		0.000	1
Total Facility		22.90	36.00	198.05	70.48	0.0000	0.000	

Values shown for a single zone without multipliers. Total Facility includes multipliers.

Total Outdoor Air by Zone

	Mechanical Ventilation [m3]	Natural Ventilation [m3]	Total Ventilation [m3]	Infiltration [m3]	Total Ventilation and Infiltration [m3]	Dynamic Target Ventilation - Voz-dyn [m3]	Time Below Voz-dyn [hr]	Time At Voz-dyn [hr]	Time Above Voz-dyn [hr]	Time Above Zero When Unoccupied [hr]	Zone Multiplier
THERMAL ZONE 1	0.00	0.00	0.00	682061.22	682061.22	1522956.58	2610.00	0.00	0.00	0.00	1
Total Facility	0.00	0.00	0.00	682061.22	682061.22	1522956.58	2610.00	0.00	0.00	0.00	

Values shown for a single zone without multipliers. Total Facility includes multipliers.

Average Outdoor Air During Occupancy by Zone - Flow Rates

	Mechanical Ventilation [m3/s]	Natural Ventilation [m3/s]	Total Ventilation [m3/s]	Infiltration [m3/s]	Total Ventilation and Infiltration [m3/s]	Dynamic Target Ventilation - Voz-dyn [m3/s]	Time Below Voz-dyn [hr]	Time At Voz-dyn [hr]	Time Above Voz-dyn [hr]	Zone Multiplier
THERMAL ZONE 1	0.0000	0.0000	0.0000	0.0090	0.0090	0.1621	2610.00	0.00	0.00	1
Total Facility	0.0000	0.0000	0.0000	0.0090	0.0090	0.1621	2610.00	0.00	0.00	

Values shown for a single zone without multipliers. Total Facility includes multipliers.

Total Outdoor Air by AirLoop

	Mechanical Ventilation [m3]	Natural Ventilation [m3]	Total Ventilation [m3]	Sum Zone Dynamic Target Ventilation - Voz-sum-dyn [m3]	Time Below Voz-sum-dyn [hr]	Time At Voz-sum-dyn [hr]	Time Above Voz-sum-dyn [hr]	Time Above Zero When Unoccupied [hr]
None								

Values shown include multipliers.

Average Outdoor Air During Occupancy by AirLoop

	Mechanical Ventilation [m3/s]	Natural Ventilation [m3/s]	Total Ventilation [m3/s]	Sum Zone Dynamic Target Ventilation - Voz-sum-dyn [m3/s]	Time Below Voz-sum-dyn [hr]	Time At Voz-sum-dyn [hr]	Time Above Voz-sum-dyn [hr]
None							

Values shown include multipliers.

Outdoor Air Controller Limiting Factors by AirLoop

	No Limiting Factor [hr]	Limits and Scheduled	Economizer [hr]	Exhaust Flow [hr]	Mixed Air Flow [hr]	High Humidity	Demand Controlled	Night Ventilation	Demand Limiting	Energy Management

		Limits [hr]				[hr]	Ventilation [hr]	[hr]	[hr]	System [hr]
None										

Average Outdoor Air for Limiting Factors During Occupancy

	No Limiting Factor [m3/s]	Limits and Scheduled Limits [m3/s]	Economizer [m3/s]	Exhaust Flow [m3/s]	Mixed Air Flow [m3/s]	High Humidity [m3/s]	Demand Controlled Ventilation [m3/s]	Night Ventilation [m3/s]	Demand Limiting [m3/s]	Energy Management System [m3/s]
None										

Values shown include multipliers.

Report: **Object Count Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Surfaces by Class

	Total	Outdoors
Wall	4	4
Floor	1	1
Roof	1	1
Internal Mass	0	0
Building Detached Shading	0	0
Fixed Detached Shading	0	0
Window	4	4
Door	1	1
Glass Door	0	0
Shading	0	0
Overhang	0	0
Fin	0	0
Tubular Daylighting Device Dome	0	0
Tubular Daylighting Device Diffuser	0	0

HVAC

	Count
HVAC Air Loops	0
Conditioned Zones	1
Unconditioned Zones	0
Supply Plenums	0
Return Plenums	0

Input Fields

	Count
IDF Objects	398
Defaulted Fields	138
Fields with Defaults	651
Autosized Fields	12
Autosizable Fields	32
Autocalculated Fields	29
Autocalculatable Fields	29

Report: **Energy Meters** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Annual and Peak Values - Electricity

	Electricity Annual Value [GJ]	Electricity Minimum Value [W]	Timestamp of Minimum {TIMESTAMP}	Electricity Maximum Value [W]	Timestamp of Maximum {TIMESTAMP}
Electricity:Facility	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
Electricity:HVAC	7.15	0.00	21-MAR-00:10	1318.60	25-DEC-08:10
Heating:Electricity	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
General:Heating:Electricity	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
Electricity:Building	2.84	0.00	21-MAR-00:10	304.51	21-MAR-08:10
Electricity:Zone:THERMAL ZONE 1	2.84	0.00	21-MAR-00:10	304.51	21-MAR-08:10
Electricity:SpaceType:LECTURE HALL 1	2.84	0.00	21-MAR-00:10	304.51	21-MAR-08:10
InteriorLights:Electricity	2.50	0.00	21-MAR-00:10	266.28	21-MAR-08:10
InteriorLights:Electricity:Zone:THERMAL ZONE 1	2.50	0.00	21-MAR-00:10	266.28	21-MAR-08:10
InteriorLights:Electricity:SpaceType:LECTURE HALL 1	2.50	0.00	21-MAR-00:10	266.28	21-MAR-08:10
General:InteriorLights:Electricity	2.50	0.00	21-MAR-00:10	266.28	21-MAR-08:10
General:InteriorLights:Electricity:Zone:THERMAL ZONE 1	2.50	0.00	21-MAR-00:10	266.28	21-MAR-08:10
General:InteriorLights:Electricity:SpaceType:LECTURE HALL 1	2.50	0.00	21-MAR-00:10	266.28	21-MAR-08:10
InteriorEquipment:Electricity	0.34	0.00	21-MAR-00:10	38.23	21-MAR-08:10
InteriorEquipment:Electricity:Zone:THERMAL ZONE 1	0.34	0.00	21-MAR-00:10	38.23	21-MAR-08:10
InteriorEquipment:Electricity:SpaceType:LECTURE HALL 1	0.34	0.00	21-MAR-00:10	38.23	21-MAR-08:10
General:InteriorEquipment:Electricity	0.34	0.00	21-MAR-00:10	38.23	21-MAR-08:10
General:InteriorEquipment:Electricity:Zone:THERMAL ZONE 1	0.34	0.00	21-MAR-00:10	38.23	21-MAR-08:10
General:InteriorEquipment:Electricity:SpaceType:LECTURE HALL 1	0.34	0.00	21-MAR-00:10	38.23	21-MAR-08:10
ElectricityPurchased:Facility	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
ElectricityPurchased:Plant	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
Cogeneration:ElectricityPurchased	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
General:Cogeneration:ElectricityPurchased	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
ElectricitySurplusSold:Facility	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
ElectricitySurplusSold:Plant	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
Cogeneration:ElectricitySurplusSold	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
General:Cogeneration:ElectricitySurplusSold	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
ElectricityNet:Facility	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
ElectricityNet:Plant	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
Cogeneration:ElectricityNet	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
General:Cogeneration:ElectricityNet	9.99	0.00	21-MAR-00:10	1623.11	25-DEC-08:10
Fans:Electricity	0.37	0.00	21-MAR-00:10	41.11	25-DEC-08:10
General:Fans:Electricity	0.37	0.00	21-MAR-00:10	41.11	25-DEC-08:10
Cooling:Electricity	6.79	0.00	21-MAR-00:10	1277.49	25-DEC-08:10
General:Cooling:Electricity	6.79	0.00	21-MAR-00:10	1277.49	25-DEC-08:10

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Natural Gas

	Natural Gas Annual Value [GJ]	Natural Gas Minimum Value [W]	Timestamp of Minimum {TIMESTAMP}	Natural Gas Maximum Value [W]	Timestamp of Maximum {TIMESTAMP}
None					

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Cooling

	Cooling Annual Value [GJ]	Cooling Minimum Value [W]	Timestamp of Minimum {TIMESTAMP}	Cooling Maximum Value [W]	Timestamp of Maximum {TIMESTAMP}
None					

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Water

	Annual Value [m3]	Minimum Value [m3/s]	Timestamp of Minimum {TIMESTAMP}	Maximum Value [m3/s]	Timestamp of Maximum {TIMESTAMP}
None					

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Other by Weight/Mass

	Annual Value [kg]	Minimum Value [kg/s]	Timestamp of Minimum {TIMESTAMP}	Maximum Value [kg/s]	Timestamp of Maximum {TIMESTAMP}
Carbon Equivalent:Facility	0.00	0.000	21-MAR-00:10	0.000	21-MAR-00:10
CarbonEquivalentEmissions:Carbon Equivalent	0.00	0.000	21-MAR-00:10	0.000	21-MAR-00:10

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Other Volumetric

	Annual Value [m3]	Minimum Value [m3/s]	Timestamp of Minimum {TIMESTAMP}	Maximum Value [m3/s]	Timestamp of Maximum {TIMESTAMP}
None					

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Other Liquid/Gas

	Annual Value [L]	Minimum Value [L]	Timestamp of Minimum {TIMESTAMP}	Maximum Value [L]	Timestamp of Maximum {TIMESTAMP}
None					

Values shown are for all completed run periods - including any simulations run during sizing periods

Annual and Peak Values - Other

	Annual Value [GJ]	Minimum Value [W]	Timestamp of Minimum {TIMESTAMP}	Maximum Value [W]	Timestamp of Maximum {TIMESTAMP}
EnergyTransfer:Facility	51.05	0.00	21-MAR-00:10	8748.24	25-DEC-08:10
EnergyTransfer:HVAC	31.13	0.00	21-MAR-00:10	6610.13	25-DEC-08:10
HeatingCoils:EnergyTransfer	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
EnergyTransfer:Building	19.92	0.00	21-MAR-00:10	3059.90	01-JUN-12:00
EnergyTransfer:Zone:THERMAL ZONE 1	19.92	0.00	21-MAR-00:10	3059.90	01-JUN-12:00
Heating:EnergyTransfer	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
Heating:EnergyTransfer:Zone:THERMAL ZONE 1	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
General:Heating:EnergyTransfer	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
General:Heating:EnergyTransfer:Zone:THERMAL ZONE 1	0.00	0.00	21-MAR-00:10	0.00	21-MAR-00:10
Cooling:EnergyTransfer	19.92	0.00	21-MAR-00:10	3059.90	01-JUN-12:00
Cooling:EnergyTransfer:Zone:THERMAL ZONE 1	19.92	0.00	21-MAR-00:10	3059.90	01-JUN-12:00
General:Cooling:EnergyTransfer	19.92	0.00	21-MAR-00:10	3059.90	01-JUN-12:00
General:Cooling:EnergyTransfer:Zone:THERMAL ZONE 1	19.92	0.00	21-MAR-00:10	3059.90	01-JUN-12:00
CoolingCoils:EnergyTransfer	31.13	0.00	21-MAR-00:10	6610.13	25-DEC-08:10

Values shown are for all completed run periods - including any simulations run during sizing periods

---

Report: **Sensible Heat Gain Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Annual Building Sensible Heat Gain Components

	HVAC Zone Eq & Other Sensible Air Heating [GJ]	HVAC Zone Eq & Other Sensible Air Cooling [GJ]	HVAC Terminal Unit Sensible Air Heating [GJ]	HVAC Terminal Unit Sensible Air Cooling [GJ]	HVAC Input Heated Surface Heating [GJ]	HVAC Input Cooled Surface Cooling [GJ]	People Sensible Heat Addition [GJ]	Lights Sensible Heat Addition [GJ]	Equipment Sensible Heat Addition [GJ]	Window Heat Addition [GJ]	Interzone Air Transfer Heat Addition [GJ]	Infiltration Heat Addition [GJ]	Opaque Surface Conduction and Other Heat Addition [GJ]	Equipment Sensible Heat Removal [GJ]
THERMAL ZONE 1	0.000	-19.854	0.000	0.000	0.000	0.000	16.465	2.492	0.337	16.455	0.000	2.638	0.000	0.000

Total Facility	0.000	-19.854	0.000	0.000	0.000	0.000	16.465	2.492	0.337	16.455	0.000	2.638	0.000	0.000

Peak Cooling Sensible Heat Gain Components

	Time of Peak {TIMESTAMP}	HVAC Zone Eq & Other Sensible Air Heating [W]	HVAC Zone Eq & Other Sensible Air Cooling [W]	HVAC Terminal Unit Sensible Air Heating [W]	HVAC Terminal Unit Sensible Air Cooling [W]	HVAC Input Heated Surface Heating [W]	HVAC Input Cooled Surface Cooling [W]	People Sensible Heat Addition [W]	Lights Sensible Heat Addition [W]	Equipment Sensible Heat Addition [W]	Window Heat Addition [W]	Interzone Air Transfer Heat Addition [W]	Infiltration Heat Addition [W]	Op Su Condu and Add
THERMAL ZONE 1	01-JUN-11:00	0.00	-3059.55	0.00	0.00	0.00	0.00	1991.95	266.28	38.23	2800.09	0.00	86.40	
Total Facility	01-JUN-11:00	0.00	-3059.55	0.00	0.00	0.00	0.00	1991.95	266.28	38.23	2800.09	0.00	86.40	

Peak Heating Sensible Heat Gain Components

	Time of Peak {TIMESTAMP}	HVAC Zone Eq & Other Sensible Air Heating [W]	HVAC Zone Eq & Other Sensible Air Cooling [W]	HVAC Terminal Unit Sensible Air Heating [W]	HVAC Terminal Unit Sensible Air Cooling [W]	HVAC Input Heated Surface Heating [W]	HVAC Input Cooled Surface Cooling [W]	People Sensible Heat Addition [W]	Lights Sensible Heat Addition [W]	Equipment Sensible Heat Addition [W]	Window Heat Addition [W]	Interzone Air Transfer Heat Addition [W]	Infiltration Heat Addition [W]	Op Su Condu and Add
THERMAL ZONE 1	-	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Total Facility	-	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

Report: **Standard 62.1 Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

System Ventilation Requirements for Cooling

	Sum of Zone Primary Air Flow - Vpz-sum [m3/s]	System Population - Ps	Sum of Zone Population - Pz-sum	Occupant Diversity - D	Origin of D	Uncorrected Outdoor Air Intake Airflow - Vou [m3/s]	System Primary Airflow - Vps [m3/s]	Average Outdoor Air Fraction - Xs	System Ventilation Efficiency - Ev	Calculation Method for Ev	Outdoor Air Intake Flow - Vot [m3/s]	Percent Outdoor Air - %OA	Environment Name of Peak System Population - Ps	Date and Time of Last Peak System Population - Ps
None														

System Ventilation Requirements for Heating

	Sum of Zone Primary Air Flow - Vpz-sum [m3/s]	System Population - Ps	Sum of Zone Population - Pz-sum	Occupant Diversity - D	Origin of D	Uncorrected Outdoor Air Intake Airflow - Vou [m3/s]	System Primary Airflow - Vps [m3/s]	Average Outdoor Air Fraction - Xs	System Ventilation Efficiency - Ev	Calculation Method for Ev	Outdoor Air Intake Flow Vot [m3/s]	Percent Outdoor Air - %OA	Environment Name of Peak System Population - Ps	Date and Time of Last Peak System Population - Ps
None														

Zone Ventilation Parameters

	AirLoop Name	People Outdoor Air Rate - Rp [m3/s-person]	Zone Population - Pz	Area Outdoor Air Rate - Ra [m3/s-m2]	Zone Floor Area - Az [m2]	Breathing Zone Outdoor Airflow - Vbz [m3/s]	Cooling Zone Air Distribution Effectiveness - Ez-clg	Cooling Zone Outdoor Airflow - Voz-clg [m3/s]	Heating Zone Air Distribution Effectiveness - Ez-htg	Heating Zone Outdoor Airflow - Voz-htg [m3/s]
None										

System Ventilation Parameters

	People Outdoor Air Rate - Rp [m3/s-person]	Sum of Zone Population - Pz-sum	Area Outdoor Air Rate - Ra [m3/s-m2]	Sum of Zone Floor Area - Az-sum [m2]	Breathing Zone Outdoor Airflow - Vbz [m3/s]	Cooling Zone Outdoor Airflow - Voz-clg [m3/s]	Heating Zone Outdoor Airflow - Voz-htg [m3/s]
None							

Zone Ventilation Calculations for Cooling Design

	AirLoop Name	Box Type	Zone Primary Airflow - Vpz [m3/s]	Zone Discharge Airflow - Vdz [m3/s]	Minimum Zone Primary Airflow - Vpz-min [m3/s]	Is Vpz-min calculated using the Standard 62.1 Simplified Procedure?	Zone Outdoor Airflow Cooling - Voz-clg [m3/s]	Primary Outdoor Air Fraction - Zpz	Primary Air Fraction - Ep	Secondary Recirculation Fraction- Er	Supply Air Fraction- Fa	Mixed Air Fraction - Fb	Outdoor Air Fraction - Fc	Zone Ventilation Efficiency - Evz
None														

System Ventilation Calculations for Cooling Design

	Sum of Zone Primary Airflow - Vpz-sum [m3/s]	System Primary Airflow - Vps [m3/s]	Sum of Zone Discharge Airflow - Vdz-sum [m3/s]	Sum of Min Zone Primary Airflow - Vpz-min [m3/s]	Zone Outdoor Airflow Cooling - Voz-clg [m3/s]	Zone Ventilation Efficiency - Evz-min
None						

Zone Ventilation Calculations for Heating Design

	AirLoop Name	Box Type	Zone Primary Airflow - Vpz [m3/s]	Zone Discharge Airflow - Vdz [m3/s]	Minimum Zone Primary Airflow - Vpz-min [m3/s]	Is Vpz-min calculated using the Standard 62.1 Simplified Procedure?	Zone Outdoor Airflow Heating - Voz-htg [m3/s]	Primary Outdoor Air Fraction - Zpz	Primary Air Fraction - Ep	Secondary Recirculation Fraction- Er	Supply Air Fraction- Fa	Mixed Air Fraction - Fb	Outdoor Air Fraction - Fc	Zone Ventilation Efficiency - Evz
None														

System Ventilation Calculations for Heating Design

	Sum of Zone Primary Airflow - Vpz-sum [m3/s]	System Primary Airflow - Vps [m3/s]	Sum of Zone Discharge Airflow - Vdz-sum [m3/s]	Sum of Min Zone Primary Airflow - Vpz-min [m3/s]	Zone Outdoor Airflow Heating - Voz-htg [m3/s]	Zone Ventilation Efficiency - Evz-min
None						

Report: **LEED Summary**

Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Sec1.1A-General Information

	Data
Weather File	RUN PERIOD 1 ** Quixeramobim CE BRA INMET WMO#=825860
Total gross floor area [m2]	70.48

EAp2-1. Space Usage Type

	Space Area [m2]	Regularly Occupied Area [m2]	Unconditioned Area [m2]	Typical Hours/Week in Operation [hr/wk]
THERMAL ZONE 1	70.48	70.48	0.00	49.86
Totals	70.48	70.48	0.00	

EAp2-2. Advisory Messages

	Data
Number of hours heating loads not met	0.00
Number of hours cooling loads not met	2.67
Number of hours not met	2.67

EAp2-3. Energy Type Summary

	Utility Rate	Virtual Rate [$/unit energy]	Units of Energy	Units of Demand
None				

EAp2-4/5. Performance Rating Method Compliance

	Electricity Energy Use [GJ]	Electricity Demand [W]	Natural Gas Energy Use [GJ]	Natural Gas Demand [W]	Gasoline Use [GJ]	Gasoline Demand [W]	Diesel Use [GJ]	Diesel Demand [W]	Coal Use [GJ]	Coal Demand [W]	Fuel Oil No 1 Use [GJ]	Fuel Oil No 1 Demand [W]	Fuel Oil No 2 Use [GJ]	Fuel Oil No 2 Demand [W]	Propane Use [GJ]	Propane Demand [W]
Heating -- General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cooling -- General	6.76	1277.49	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Lighting -- General	2.49	266.28	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Lighting -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Interior Equipment -- General	0.34	38.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Exterior Equipment -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Fans -- General	0.37	41.11	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Pumps -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Rejection -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Humidification -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Heat Recovery -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Water Systems -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Refrigeration -- Not Subdivided	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Generators -- General	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

EAp2-6. Energy Use Summary

	Process Subtotal [GJ]	Total Energy Use [GJ]
Electricity	0.34	9.96
Natural Gas	0.00	0.00
Additional	0.00	0.00
Total	0.34	9.96

EAp2-7. Energy Cost Summary

	Process Subtotal [$]	Total Energy Cost [$]
Electricity	0.00	
Natural Gas	0.00	
Additional	0.00	

Total	0.00	

Process energy cost based on ratio of process to total energy.

L-1. Renewable Energy Source Summary

	Rated Capacity [kW]	Annual Energy Generated [GJ]
Photovoltaic	0.00	0.00
Wind	0.00	0.00

EAp2-17a. Energy Use Intensity - Electricity

	Electricity [MJ/m2]
Interior Lighting (All)	35.36
Space Heating	0.00
Space Cooling	95.96
Fans (All)	5.20
Service Water Heating	0.00
Receptacle Equipment	4.78
Miscellaneous (All)	141.31
Subtotal	141.31

EAp2-17b. Energy Use Intensity - Natural Gas

	Natural Gas [MJ/m2]
Space Heating	0.00
Service Water Heating	0.00
Miscellaneous (All)	0.00
Subtotal	0.00

EAp2-17c. Energy Use Intensity - Additional

	Additional [MJ/m2]
Subtotal	0.00
Miscellaneous	0.00

EAp2-18. End Use Percentage

	Percent [%]
Interior Lighting (All)	25.03
Space Heating	0.00
Space Cooling	67.91
Fans (All)	3.68
Service Water Heating	0.00
Receptacle Equipment	3.38
Miscellaneous	-0.00

Schedules-Equivalent Full Load Hours (Schedule Type=Fraction)

	Equivalent Full Load Hours of Operation Per Year [hr]	Hours > 1% [hr]
MEDIUM OFFICE BLDG EQUIP	4737.	8760.
MEDIUM OFFICE BLDG OCC	2834.	5252.
MEDIUM OFFICE INFIL QUARTER ON	5172.	8760.
OFFICE BLDG EQUIP	4737.	8760.
OFFICE BLDG LIGHT	3225.	8760.
OFFICE INFIL QUARTER ON	5172.	8760.
OFFICE MISC OCC	1508.	5252.
OFFICE WORK OCC	2595.	5252.

Schedules-SetPoints (Schedule Type=Temperature)

	First Object Used	Month Assumed	11am First Wednesday [C]	Days with Same 11am Value	11pm First Wednesday [C]	Days with Same 11pm Value
SCHEDULE RULESET 1 QXD LECTURE HALL HEATING SETPOINT TEMPERATURE	THERMOSTAT SETPOINT DUAL SETPOINT 1	July	15.00	365	15.00	365
SCHEDULE RULESET 1 QXD LECTURE HALL COOLING SETPOINT TEMPERATURE	THERMOSTAT SETPOINT DUAL SETPOINT 1	January	22.00	365	40.00	365

Report: **Annual CO2 Resilience Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

CO2 Level Hours

	Safe (<= 1000 ppm) [hr]	Caution (> 1000, <= 5000 ppm) [hr]	Hazard (> 5000 ppm) [hr]
None			

CO2 Level OccupantHours

	Safe (<= 1000 ppm) [hr]	Caution (> 1000, <= 5000 ppm) [hr]	Hazard (> 5000 ppm) [hr]
None			

CO2 Level OccupiedHours

	Safe (<= 1000 ppm) [hr]	Caution (> 1000, <= 5000 ppm) [hr]	Hazard (> 5000 ppm) [hr]
None			

Report: **Annual Visual Resilience Summary** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Illuminance Level Hours

	A Bit Dark (<= 100 lux) [hr]	Dim (> 100, <= 300 lux) [hr]	Adequate (> 300, <= 500 lux) [hr]	Bright (>500 lux) [hr]
None				

Illuminance Level OccupantHours

	A Bit Dark (<= 100 lux) [hr]	Dim (> 100, <= 300 lux) [hr]	Adequate (> 300, <= 500 lux) [hr]	Bright (>500 lux) [hr]
None				

Illuminance Level OccupiedHours

	A Bit Dark (<= 100 lux) [hr]	Dim (> 100, <= 300 lux) [hr]	Adequate (> 300, <= 500 lux) [hr]	Bright (>500 lux) [hr]
None				

Report: **BUILDING ENERGY PERFORMANCE - ELECTRICITY** Table of Contents

For: **Meter**

Timestamp: **2026-10-22 22:29:08**

Custom Monthly Report

	INTERIORLIGHTS:ELECTRICITY [J]	EXTERIORLIGHTS:ELECTRICITY []	INTERIOREQUIPMENT:ELECTRICITY [J]	EXTERIOREQUIPMENT:ELE
January	2.108930E+08	0.00	28515613.75	
February	1.917209E+08	0.00	25923285.23	

March	2.204790E+08	0.00	29811778.02	
April	1.917209E+08	0.00	25923285.23	
May	2.204790E+08	0.00	29811778.02	
June	2.108930E+08	0.00	28515613.75	
July	2.013069E+08	0.00	27219449.49	
August	2.204790E+08	0.00	29811778.02	
September	2.013069E+08	0.00	27219449.49	
October	2.108930E+08	0.00	28515613.75	
November	2.108930E+08	0.00	28515613.75	
December	2.013069E+08	0.00	27219449.49	
Annual Sum or Average	2.492371E+09	0.00	3.370027E+08	
Minimum of Months	1.917209E+08	0.00	25923285.23	
Maximum of Months	2.204790E+08	0.00	29811778.02	

Report: **BUILDING ENERGY PERFORMANCE - ELECTRICITY PEAK DEMAND** Table of Contents

For: **Meter**

Timestamp: **2026-10-22 22:29:08**

Custom Monthly Report

	ELECTRICITY:FACILITY {Maximum} [W]	ELECTRICITY:FACILITY {TIMESTAMP}	INTERIORLIGHTS:ELECTRICITY {AT MAX/MIN} [W]	EXTERIORLIGHTS:ELECTRICITY []	INTERIOREQU
January	1561.98	18-JAN-08:19	266.28	0.00	
February	1525.19	20-FEB-08:19	266.28	0.00	
March	1471.94	24-MAR-08:19	266.28	0.00	
April	1455.81	03-APR-08:19	266.28	0.00	
May	1532.97	17-MAY-08:19	266.28	0.00	
June	1425.83	02-JUN-08:19	266.28	0.00	
July	1340.33	21-JUL-08:19	266.28	0.00	
August	1407.58	23-AUG-08:19	266.28	0.00	
September	1351.03	29-SEP-08:19	266.28	0.00	
October	1475.90	25-OCT-08:19	266.28	0.00	
November	1466.34	09-NOV-08:19	266.28	0.00	
December	1623.11	25-DEC-08:19	266.28	0.00	
Annual Sum or Average				0.00	
Minimum of Months	1340.33		266.28	0.00	
Maximum of Months	1623.11		266.28	0.00	

Report: **Life-Cycle Cost Report** Table of Contents

For: **Entire Facility**

Timestamp: **2026-10-22 22:29:08**

Life-Cycle Cost Parameters

	Value
Name	LIFE CYCLE COST PARAMETERS
Discounting Convention	EndOfYear
Inflation Approach	ConstantDollar

Real Discount Rate	0.0300
Nominal Discount Rate	-- N/A --
Inflation	-- N/A --
Base Date	January 2011
Service Date	January 2011
Length of Study Period in Years	25
Tax rate	0.0000
Depreciation Method	None

Use Price Escalation

	U.S. AVG COMMERCIAL-ELECTRICITY	U.S. AVG COMMERCIAL-DISTILLATE OIL	U.S. AVG COMMERCIAL-RESIDUAL OIL	U.S. AVG COMMERCIAL-NATURAL GAS	U.S. AVG COMMERCIAL-COAL
Resource	Electricity	FuelOilNo1	FuelOilNo2	NaturalGas	Coal
Start Date	January 2011	January 2011	January 2011	January 2011	January 2011
1	0.983800	0.971400	0.846900	0.982300	0.997000
2	0.973000	0.973000	0.825700	0.955700	1.008900
3	0.963200	0.994200	0.868100	0.927900	1.008900
4	0.961100	1.016400	0.898800	0.925700	0.994100
5	0.957100	1.054100	0.928900	0.934600	0.994100
6	0.955300	1.092800	0.960400	0.941200	1.000000
7	0.953900	1.126700	0.989700	0.951200	1.003000
8	0.952100	1.158000	1.007500	0.964500	1.005900
9	0.954600	1.179200	1.031400	0.985600	1.008900
10	0.955000	1.196700	1.055400	1.006700	1.011900
11	0.955300	1.220000	1.086100	1.022200	1.014800
12	0.956400	1.233300	1.127800	1.041000	1.017800
13	0.957500	1.256600	1.149700	1.061000	1.020800
14	0.959600	1.270900	1.162000	1.078700	1.026700
15	0.961800	1.282600	1.174300	1.094200	1.029700
16	0.961400	1.298500	1.185200	1.109800	1.035600
17	0.961800	1.310200	1.194800	1.122000	1.041500
18	0.961800	1.325000	1.203700	1.130800	1.053400
19	0.959300	1.326100	1.207100	1.138600	1.056400
20	0.958900	1.328200	1.211900	1.148600	1.059300
21	0.960700	1.332400	1.213900	1.161900	1.065300
22	0.962500	1.335600	1.219400	1.176300	1.071200
23	0.965000	1.343100	1.227600	1.191800	1.074200
24	0.970800	1.351000	1.236500	1.211800	1.080100
25	0.975100	1.356800	1.242000	1.228400	1.083100

Cash Flow for Recurring and Nonrecurring Costs (Without Escalation)

	DEFAULT COST
	Nonrecurring
January 2011	0.00
January 2012	0.00
January 2013	0.00
January 2014	0.00
January 2015	0.00
January 2016	0.00
January 2017	0.00
January 2018	0.00
January 2019	0.00
January 2020	0.00
January 2021	0.00

January 2022	0.00
January 2023	0.00
January 2024	0.00
January 2025	0.00
January 2026	0.00
January 2027	0.00
January 2028	0.00
January 2029	0.00
January 2030	0.00
January 2031	0.00
January 2032	0.00
January 2033	0.00
January 2034	0.00
January 2035	0.00

Energy and Water Cost Cash Flows (Without Escalation)

	Total
January 2011	0.00
January 2012	0.00
January 2013	0.00
January 2014	0.00
January 2015	0.00
January 2016	0.00
January 2017	0.00
January 2018	0.00
January 2019	0.00
January 2020	0.00
January 2021	0.00
January 2022	0.00
January 2023	0.00
January 2024	0.00
January 2025	0.00
January 2026	0.00
January 2027	0.00
January 2028	0.00
January 2029	0.00
January 2030	0.00
January 2031	0.00
January 2032	0.00
January 2033	0.00
January 2034	0.00
January 2035	0.00

Energy and Water Cost Cash Flows (With Escalation)

	Total
January 2011	0.00
January 2012	0.00
January 2013	0.00
January 2014	0.00
January 2015	0.00
January 2016	0.00
January 2017	0.00
January 2018	0.00
January 2019	0.00

January 2020	0.00
January 2021	0.00
January 2022	0.00
January 2023	0.00
January 2024	0.00
January 2025	0.00
January 2026	0.00
January 2027	0.00
January 2028	0.00
January 2029	0.00
January 2030	0.00
January 2031	0.00
January 2032	0.00
January 2033	0.00
January 2034	0.00
January 2035	0.00

Capital Cash Flow by Category (Without Escalation)

	Construction	Salvage	OtherCapital	Total
January 2011	0.00	0.00	0.00	0.00
January 2012	0.00	0.00	0.00	0.00
January 2013	0.00	0.00	0.00	0.00
January 2014	0.00	0.00	0.00	0.00
January 2015	0.00	0.00	0.00	0.00
January 2016	0.00	0.00	0.00	0.00
January 2017	0.00	0.00	0.00	0.00
January 2018	0.00	0.00	0.00	0.00
January 2019	0.00	0.00	0.00	0.00
January 2020	0.00	0.00	0.00	0.00
January 2021	0.00	0.00	0.00	0.00
January 2022	0.00	0.00	0.00	0.00
January 2023	0.00	0.00	0.00	0.00
January 2024	0.00	0.00	0.00	0.00
January 2025	0.00	0.00	0.00	0.00
January 2026	0.00	0.00	0.00	0.00
January 2027	0.00	0.00	0.00	0.00
January 2028	0.00	0.00	0.00	0.00
January 2029	0.00	0.00	0.00	0.00
January 2030	0.00	0.00	0.00	0.00
January 2031	0.00	0.00	0.00	0.00
January 2032	0.00	0.00	0.00	0.00
January 2033	0.00	0.00	0.00	0.00
January 2034	0.00	0.00	0.00	0.00
January 2035	0.00	0.00	0.00	0.00

Operating Cash Flow by Category (Without Escalation)

	Maintenance	Repair	Operation	Replacement	MinorOverhaul	MajorOverhaul	OtherOperational	Water	Energy	Total
January 2011	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2012	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2013	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2014	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2015	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2016	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2017	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

January 2018	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2019	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2020	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2021	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2022	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2023	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2024	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2025	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2026	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2027	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2028	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2029	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2030	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2031	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2032	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2033	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2034	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2035	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Operating Cash Flow by Category (With Escalation)

	Maintenance	Repair	Operation	Replacement	MinorOverhaul	MajorOverhaul	OtherOperational	Water	Energy	Total
January 2011	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2012	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2013	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2014	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2015	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2016	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2017	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2018	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2019	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2020	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2021	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2022	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2023	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2024	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2025	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2026	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2027	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2028	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2029	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2030	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2031	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2032	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2033	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2034	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
January 2035	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Monthly Total Cash Flow (Without Escalation)

	January	February	March	April	May	June	July	August	September	October	November	December
2011	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2012	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2013	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2014	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2015	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

2016	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2017	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2018	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2019	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2020	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2021	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2022	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2023	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2024	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2025	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2026	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2027	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2028	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2029	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2030	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2031	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2032	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2033	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2034	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2035	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Present Value for Recurring, Nonrecurring and Energy Costs (Before Tax)

	Category	Kind	Cost	Present Value	Present Value Factor
DEFAULT COST	Construction	Nonrecurring	0.00	0.00	-
TOTAL				0.00	

Present Value by Category

	Present Value
Maintenance	0.00
Repair	0.00
Operation	0.00
Replacement	0.00
Minor Overhaul	0.00
Major Overhaul	0.00
Other Operational	0.00
Water	0.00
Energy	0.00
Total Operation	0.00
Construction	0.00
Salvage	0.00
Other Capital	0.00
Total Capital	0.00
Total Energy	0.00
Grand Total	0.00

Present Value by Year

	Total Cost (Without Escalation)	Total Cost (With Escalation)	Present Value of Costs
January 2011	0.00	0.00	0.00
January 2012	0.00	0.00	0.00
January 2013	0.00	0.00	0.00
January 2014	0.00	0.00	0.00
January 2015	0.00	0.00	0.00
January 2016	0.00	0.00	0.00
January 2017	0.00	0.00	0.00

January 2018	0.00	0.00	0.00
January 2019	0.00	0.00	0.00
January 2020	0.00	0.00	0.00
January 2021	0.00	0.00	0.00
January 2022	0.00	0.00	0.00
January 2023	0.00	0.00	0.00
January 2024	0.00	0.00	0.00
January 2025	0.00	0.00	0.00
January 2026	0.00	0.00	0.00
January 2027	0.00	0.00	0.00
January 2028	0.00	0.00	0.00
January 2029	0.00	0.00	0.00
January 2030	0.00	0.00	0.00
January 2031	0.00	0.00	0.00
January 2032	0.00	0.00	0.00
January 2033	0.00	0.00	0.00
January 2034	0.00	0.00	0.00
January 2035	0.00	0.00	0.00
TOTAL			0.00